

ELEV. TOP OF CASING 736.10

10-5 WATER

10-5 725.68

20-0 SAND & GRAVEL

30-5 705.68

17-4 SANDY SHALE

47-9 688.35

LOST WATER AT 33-0

30-9 SANDSTONE

0-4	78-6	657.60	CLAY SHALE
0-3	79-3	656.85	
2-1	79-7	656.52	SANDSTONE
0-10	81-8	654.44	SANDY CLAY SHALE
0-11	82-6	653.60	BLACK SLATE
	83-5	652.68	CANNEL SLATE

6-5 COAL

89-10 646.27

4-0 FIRE CLAY SHALE

0-4	94-8	641.44	LIMESTONE
1-0	95-8	640.44	
	96-0	640.10	LIME SHALE

7- CLAY SHALE

103-11 633.02

0-2 1/2 DIRTY COAL

1-0 1/2 COAL

0-11 HIGH ASH

3-3 1/2 COAL

0-1/4 BAND  
0-2 3/4 COAL  
0-1 1/2 BAND  
0-7 COAL

ALLEGHENY PITTSBURGH COAL CO  
PITTSBURGH PA

DIAMOND DRILL RECORD  
HOLE No 6  
SPRINGDALE MINE  
LOGAN'S FERRY PA

SCALE 1/4" = 10' TOTAL  
DATE Sept. 8, 1919

3960-G