



U. S. REFRATORIES CORP.

STEPHENSON — MINE

SANBOURN RUN PA. SCALE 1" = 100'

Mt. UNION, PENNA. OFFICE OF U. S. REF. CORP.

J.C.M.

U. S. REF. CORP. (SUR.)
W. C. GOSS (CLAY)

Note
 Rooms turned on 32' centres 16' wide 14' rib
 16 Acres of Height
 Tonnage 256,000 Gross Tons
 Tonnage Worked out 93,000 Gross Tons
 Balance 246,700 Gross Tons
 Conglomerate Hard Clay