

Location	Producer	Property	Type of Operation		Terrace			Date	Laboratory SO ₄ Loss - cycles	L.A.R. % Long 500 Rev.	Remarks
			Dredging	Open Pit	Outwash	Low	High				
11	George W. Yeagle	Glade Run		X	X?					25.7 25.9 41.2 34.9	
12	Brokenstraw Gravel, Inc.	Chet Kibbey		X	X					26.8 26.9	Collected at top (0-12 feet depth) of deposit; tested as PennDOT Lab. No. 68-41600. Collected at middle (12-24 feet depth) of deposit; tested as PennDOT Lab. No. 68-41603. Collected at bottom (24-36 feet depth) of deposit; tested as PennDOT Lab. No. 68-41239. The 1962 test work was done when Emlenton Limestone Co. had a short-term lease on the property.
13	Emlenton Limestone Co.	Ray Thomas pit		X	X					26.9 23.5 36.4 30.4	Tests of August 14, 1970 and September 14, 1970 when done by John H. Robinson Testing, Inc., Erie, Pa. for a Type A material. Emlenton Limestone Co. had another sample tested following the marginal results reported for the September 14, 1970 test, but the sodium sulfate test again ran close to 20. Data to support the last test were not available.
14	Hasbrouck Sand & Gravel Co.	Hydetown		X	X					25.0 35.2	Processed sample collected for testing for Type A coarse aggregate on Sept. 7, 1973. Sample represents gravel just above the water table in the pit.
15	Emlenton Limestone Co.	Reno Pit		X		X				44.4	
16	Emlenton Limestone Co.	Burkhart		X	X					42.7	May test done by John H. Robinson Testing, Inc., Erie, Pa.
17	Tionesta Sand & Gravel Co.	Coopersburg pit			X					28.7 29.9 27.5	Sample collected from below the water table in pit in September 7, 1963 and processed at Tionesta plant located at Tionesta. Processed gravel sent to PennDOT Lab. in Harrisburg to be tested for Type A coarse aggregate.
18	W. L. Dunn	Cochranon pit		X						28.0 25.3 24.1 28.3	
19	Meadville Concrete Redi-Mix Inc.			X							No test records onfile with PennDOT in Harrisburg, Pa.
20	Joseph Arendash	Arendash pit Hayfield Twp.		X	X					30.2	
21	Atlas Sand & Gravel Co.	Hadley pit		X							
22	Taylor Supply Co.			X							No test records in PennDOT High Percentage of Sand.
23	Siedel Sand & Gravel Co.	Big Bend pit		X							