



Note - We are of the opinion that this map is incorrect due to a faulty chain used in making the survey. The evidence points to one link short in the chain. (1 link is 792 inches). In making the survey it is assumed, the surveyor started at stone marked ① and ran the line running N 21° 30' E. He evidently came upon the several corners marked on the map but since his chain was one link short he got greater distances between corners than called for on map # 61-2-10. (207. map). When he reached the corner marked ② he was, according to his erroneous chain, 48 or 50 rods past the supposedly accurate location of the corner. He calculated that he should go 168.5 rods to the corner marked ③ and after measuring the 168.5 P. on his chain he found that he was about 10 rods from the corner previously established. Assuming that he was correct in his survey he continued to the eastward and tied to other old corners on the eastern property line. Subsequent surveys made over this map would likely confirm the marks on the ground due to the faulty chain.

Scale 50 rods = 1 inch

MAP
OF LANDS SITUATED IN CLAY
AND CROMWELL TOWNSHIPS
HUNTINGDON CO. PENNA.
SURVEYED FOR THE M³ UNION REFRACTORIES
CO. IN JULY AND AUG. 1911.
W. B. Mitchell

12/10/21 JH + W.W. 4. ← note this opinion will be confirmed on following future surveys on these lands.