

TREYON'T MINING COMPANY

PROPOSED MINE SEALS
longitudinal section

1st stopping inby shall be constructed with a double row of solid 8"x15"x4" concrete block and fly ash & cement slurry for a minimum distance of 5 feet between each stoppings. Second stopping shall be constructed likewise. There will be no recess into the roof because of the present concrete tunnels.

