



W. J. RAINEY CO  
MT. BRADDOCK MINE

**CUT THROUGH PROCEDURE**  
 1. DRILL AND MINE TO WITHIN 3 FEET.  
 2. CONSTRUCT STOPPING WITH DROP DOOR.  
 3. WITH DROP DOOR CLOSED, WIG THROUGH BY HAND.

\* IF INACCESSIBLE FOR INSPECTION, DRILL TEST HOLE PRIOR TO MINING.

FROM THIS LOCATION LINE, START DRILLING TEST HOLES IN ACCORDANCE WITH MINING LAW.

NOTE: ONLY ONE LIFT MAY BE MINED ON EACH BLOCK AS DIRECTION OF LIFTS WHEN ABNORMAL CONDITIONS OCCUR. NOT MORE THAN THREE LIFTS MAY BE MINED IN THE SAME DIRECTION ON ADJACENT BLOCKS.

WATER TRAPS TO BE INSTALLED UNDER STOPPINGS IN 4, 45 AND 46 ROOMS.