



LINE BRATTICE WITHIN 10' OF FACE AT ALL TIME
 AVERAGE VELOCITY 1000 FT. PER MIN.
 LINE BRATTICE MAX. CURVE
 8" DIA. BUCKLE OR EQUIVALENT
 9000 CFT. P.M. MINIMUM

LINE BRATTICE IS USED TO PROVIDE
 VENTILATION TO THE WORKING
 FACE. EXHAUST AND BLOWING
 SYSTEM USED TO WITHIN
 10' OF FACE

LEGEND OF VENTILATION SYMBOLS
 GREEN — INTAKE AIR
 ORANGE — RETURN AIR
 E — PERM. STOPPING
 H — TEMP. STOPPING
 D — PERM. DOORS
 O — TEMP. DOORS
 Z — OVERCAST
 X — CAVED AREA
 R — REGULATOR
 S — SEAL
 — 30" HAULAGE BELTS
 — 12" YELLOW-ESSON TUNNELS
 — 4" X 8" CONCRETE BLOCK ARE
 USED ON PERMANENT STOPPING
 UNDERCAST UNDERGAST ETC
 E1 1760/1

NOTE:
 I hereby certify that the mine work as shown
 on this map as of July 29, 1922, the day it was
 closed and abandoned, is true and correct
 to the best of my knowledge and belief
Michael Downey

PERMIT 225-2A PROJECTION NO.
 MAP OF
 VALLEY COAL COMPANY
 LOWER FREEPORT SEAM NO. 11 MINE (FED. NO. 36-00930)
 PINE TWP. INDIANA CO. PA.
 JAN. 1922 SCALE 1" = 100'
 DRAWN BY C. KIRBY
 SUPERVISOR PA.