



MINERAL OWNERS

GROUP I - 52 AC.	GROUP II - 26 AC.	GROUP III - 1 AC.
JOHN MCLURE I, II, III	HERMAN MCLURE I, II, III	
VYRL WHEATON I, II, III	CHARLES MCLURE I, II, III	
CYRIL PELLEGRINI I, II, III	LENE PAPPAPUTIS I, II, III	
NELL COX I, II, III	GENEVE MCLURE I, II, III	
FLORA MCLURE I, II, III	RALPH MCLURE I, II, III	
WAYNE MCLURE I, II, III	RONALD GLASSCOCK I, II, III	
BRUCE GLASSCOCK I, II, III		
MICHAEL PAPPAPUTIS I, II, III		

NOTES: 1. 50% OF THE ORIGINAL UNMINED PILLAR CROSSING A SUPPORT LINE WILL REMAIN
 2. MAXIMUM ENTRY WIDTH THROUGH SUPPORT AREAS SHALL BE 8'-0"

LEGEND

	PERMIT LIFE (SUBSIDENCE CONTROL)
	6 MONTH PROJECTION (PLAN BOUNDARY)
	INTAKE
	RETURN
	BLEEDER
	PERMANENT STOPPING
	REGULATOR
	BOXCHECK
	MANDOOR
	OVERCAST
	CHECK CURTAIN
	LOADING POINT
	BELT
	PRIMARY ESCAPEWAY
	SECONDARY ESCAPEWAY
	SURVEY STATION
	COAL CONTOUR
	SUPPORT BLOCK (50% MINING)
	PILLARED AREA
	STRUCTURE INVENTORY NUMBER
	PRE-1966 STRUCTURE
	BELT OVER TRACK
	DOOR
	COMPLETED OVERCAST

* MAIN FAN DATA:
 MANUFACTURER: FAN SYSTEMS, INC.
 TYPE: LOW PRESSURE E-HAUST
 SIZE: 72 INCHES
 SPEED: 902 RPM
 WATER USAGE: 1.0 INCHES (MAXIMUM)
 QUANTITY OF AIR: 100,000 CFM (MAXIMUM)
 PRESENT BLADE SETTING: MINIMUM (VARIABLE)

MOTOR DATA:
 MANUFACTURER: RELIANCE
 TYPE: A.C.
 HORSEPOWER: 75
 VOLTAGE: 480
 AMPERE RATING: 30

6 MONTH MINING PROJECTION #2

MEADOW RUN MINING COMPANY, INC.

MEADOW RUN MINE

PO BOX 399 BOBTOWN, PA 15315
 DUNKARD TWP GREENE CO., PA

M.S.H.A. ID No 36-07987 PA. M.D. No 30871301

SCALE: 1" = 100'

DATE: 5/1/89

PREPARED BY
 CHARBEL MINING SERVICES, INC.
 P.O. BOX 399
 BOBTOWN, PA
 412-324-5470



Robert L. Garbart