

ALL SURFACE FEATURES AND ANY UNDERGROUND MINING ACTIVITY DONE PRIOR TO FEBRUARY 16, 1992 DEPICTED ON THIS MAP WERE PROVIDED TO CHARBEL ENGINEERING BY OTHER ENGINEERING FIRMS AND DOES NOT REPRESENT AN ACTUAL FIELD SURVEY BY CHARBEL ENGINEERING

NOTES:

1. OVERLYING WAYNESBURG COAL SEAM HAS BEEN PARTIALLY SURFACE MINED AND RECLAIMED UNDERLYING THE PETTITE NO. 1 MINE PROPERTY IS AN UNDEVELOPED AREA OF THE SHANNOPIN MINE OF THE PITTSBURGH SEAM WHICH IS APPROXIMATELY 100' BELOW. SEE EXHIBIT 1 FOR ADJACENT & UNDERLYING WORKINGS.
2. SURVEYED BY CLOSED LOOP METHOD WITH AN ACCURACY OF AT LEAST 1 IN 5,000
3. THIS MAP SATISFIES THE REQUIREMENTS OF 30 CFR 751200 AND 75.372
4. PERSONS RESPONSIBLE FOR THE INFORMATION ON THIS MAP: JUNIOR GOLDEN, STEVE CLAPPER
5. NO KNOWN DRILL HOLES EXIST ON MINE PROPERTY.

- PERMIT LINE & SUBSIDENCE CONTROL PLAN BOUNDARY
- BARRIER LINE & 6 MONTH PROJECTION LINE
- INTAKE
- RETURN
- BLEEDER
- STOPPING WITH BLOCK REMOVED
- PERMANENT STOPPING
- BOXCHECK
- REGULATOR
- MANDOOR
- PROPOSED SEALS
- CHECK CURTAIN
- FRAMED CHECK CURTAIN
- LOADING POINT
- BELT
- PRIMARY ESCAPEWAY
- SECONDARY ESCAPEWAY
- SURVEY STATION
- COAL CONTOUR
- SUPPORT BLOCK (50%) MINING
- PILLARED AREA
- STRUCTURE INVENTORY NUMBER
- PRE-1966 STRUCTURE (NONE)
- BLEEDER-EVALUATION POINT
- DOOR
- COMPLETED OVERCAST
- PERMANENT MONUMENT
- STREAM INTERMITTENT
- 6 MONTH PROJECTION LINE
- GAS WELL
- STRIKE & DIP

THE AVERAGE ENTRY WIDTH IS APPROXIMATELY TWENTY FEET

MINERAL & SURFACE OWNERS
JUNIA WYON WANNY
ELSWORTH BARBOOMAN

MAIN FAN DATA (AERODYNE JUNIOR)
MANUFACTURE: JEFFREY
TYPE: LOW PRESSURE EXHAUST
SIZE: 46 FEET DIAMETER
SPEED: 770 RPM
WATER GAUGE: 0.3 INCHES
QUANTITY OF AIR: 60000 CFM
BLADE SETTING: Plywood (Variable)

MOTOR DATA
MANUFACTURE: LINCOLN
TYPE: AC 3 PHASE
HORSEPOWER: 75
VOLTAGE: 7460
AMPERE RATING: 184/92
RPM: 1775
SERIAL NO: 3619515

US&S B.M. INFORMATION
ELEVATIONS FROM U.S. & STANDARD MGR. DATUM IS 1985. 1129'
DASH LOCATED BY THE BUREAU OF COAST & GEOD. SURV. ALONG LINE 100000. 0.7 MILES WEST OF BOSTON. ELEVATION OF B.M. 4. 1128.06

SEWICKLEY SEAM

PERMITTEE: J. J. PETTITE COAL COMPANY, INC.
P. O. BOX 2429
WESTOVER, WV 26502

OPERATOR: PITT ENERGY, INC.
ROUTE 101, BOX 402-C
MORGANTOWN, WV 26505

FINAL MAP
PETTITE NO. 1 MINE

BOSTON GREENE COUNTY PENNSYLVANIA
SCALE: 1" = 400'

FINAL MAP
PITT ENERGY, INC.
NO. 1 MINE - 36 0818

