

2 FACE OFF 2 WEST  
UNIT NO. 3  
JOY 12 CM  
SECTION I.D. NO. 023-O  
MARIETTA 300HP DRUM  
SECTION I.D. NO. 024-O

HAWKINS NO. 1 AIRSHAFT - INTAKE/RETURN  
DEPTH 126.02' TOP EL. 835.02' / BOTTOM EL. 709.00' - INTAKE  
DEPTH 100.02' TOP EL. 861.5' / BOTTOM EL. 707.3' - RETURN  
INTAKE 17.0" DIA. / RETURN 20.0" DIA.  
NO. 1 FAN JOY AXIAXANE  
10' DIA. BLADE SETTING - 7.45 DEGREES, 706RPM'S  
RETURN: 45,150 CFM, 0% CH<sub>4</sub> - INTAKE: 130,000 CFM 0% CH<sub>4</sub>  
3.0" WATER GAUGE, PULLING 98 AMPS  
FAN MOTOR  
RELIANCE, 2300 VAC, 3 PH, 400 HP, 98 AMPS  
SPARE FAN MOTOR  
RELIANCE, 2300 VAC, 3 PH, 400 HP, 98 AMPS

FACE OFF 1 WEST  
UNIT NO. 3  
JOY 12 CM  
SECTION I.D. NO. 028-O  
JOY 12 CM  
SECTION I.D. NO. 026-O

AIR FLOW IS  
RESTRICTED  
DUE TO ROOF  
FALLS  
(PM)

CLYDE MINE  
I.T.E.C.  
I.D. No. 36-00967  
VENTILATION REVIEW No. R-1

LEGEND

TRACK	INTAKE
BELT	RETURN
BELT HEAD	INTAKE ESCAPEWAY
BELT BLEEDER	RETURN ESCAPEWAY
CHECK	PROPOSED STOPPING
REGULATOR	PROPOSED INTAKE
STOPPING	PROPOSED RETURN
STOPPING W/O DOOR	PROPOSED OVERCAST
OVERCAST	INTAKE SHAF
BELT AIR	RETURN SHAF
PULL RETREAT MINING COMPLETE	STOPPING W/BLOCK RMVD
SAFETY OR PARTIAL MINING ZONE	B-G BLEEDER STATION
BELT WATER SPRAY	ROOF FALL
	PROPOSED SEALS

C-215 DRN BY: R PULIG  
EXTENDED SURVEY 07/24/92

