



PARK SHAFT FANS
 Shaft Size
 One Standby
 One Operating
 #1 Jeffrey 8-111-96-Axialflow - 8 Foot Fan - Blade Position #6
 #2 Jeffrey 8-111-96-Axialflow - 8 Foot Fan - Blade Position #6
 Both Fans Direct Drive with 500 H.P., 2300 V., AC Motors
 Operating at 102 Amps, Terminal 900 R.P.M.
 Exhausting 43289 c.f.m., Terminal 900 R.P.M.
 Intake - 680,145 c.f.m.
 Top Coping Elevation - 1103.50'
 Bottom Coal Elevation - 835.68'
 Depth - 267.82'
 Entry Height - 8.1' Avg.
 Entry Width - 16.0' Avg.

