



LOETHER BLEEDER FAN  
 (FILLED)  
 7-24-02  
 Zurn/Clarage Fans Blade Position 27°  
 Motor is 250 HP, AC Motor  
 Operating at 300 Amps, Nominal 885 R.P.M.  
 Exhausting 65,704 cfm @ 13.5" W.G. @ 0.9 % CH,  
 Top Coping Elevation - 1172.7'  
 Bottom Coal Elevation - 637.7'  
 Depth - 535'  
 Entry Height - 7.0' Avg.  
 Entry Width - 17.0' Avg.

SUNDUST SHAFT FAN  
 Filled 1-04-03  
 Joy H-96 Axialflow - 8 Foot Fan - Blade Position 12°  
 Fan is Direct Drive with 500 HP, 2300 V., AC Motor  
 Operating at 80 Amps, Nominal 900 R.P.M.  
 Exhausting 240,068 cfm @ 9.2" W.G. @ 0.0 % CH,  
 Top Coping Elevation - 1096'  
 Bottom Coal Elevation - 671'  
 Depth - 425'  
 Entry Height - 7.0' Avg.  
 Entry Width - 17.0' Avg.