



ESTIMATE
TAYLOR BANK FIRE
WASHINGTON & CHURCH STS.
TAYLOR, PA.

SECTION	CUBIC YD.
1 - 2	$\frac{0 + 7100}{2} \times 24' = 310,800$
2 - 3	$\frac{7100 + 74,072}{2} \times 69' = 740,888$
3 - 4	$\frac{74,072 + 13,890}{2} \times 61' = 621,713$
4 - 5	$\frac{13,890 + 14,925}{2} \times 46' = 661,825$
5 - 6	$\frac{14,925 + 13,890}{2} \times 41' = 597,508$
6 - 7	$\frac{13,890 + 12,350}{2} \times 31' = 396,800$
7 - 8	$\frac{12,350 + 9,025}{2} \times 106' = 1,332,075$
8 - 9	$\frac{9,025 + 10,100}{2} \times 27' = 250,188$
9 - 10	$\frac{10,100 + 10,550}{2} \times 36' = 378,900$
10 - 11	$\frac{10,550 + 11,400}{2} \times 70' = 804,950$
11 - 12	$\frac{11,400 + 2,825}{2} \times 79' = 601,703$
12 - 13	$\frac{2,825 + 0}{2} \times 55' = 105,188$
TOTAL	6,823,508

6,823,508 / 27 = 252,640 cubic yards

APP'D. - P. H. 1/24/68

NORTHERN FIELD.

SURFACE MAP
SHOWING
BANK FIRE
CHURCH & WASHINGTON STS.
TAYLOR BORO, LACKAWANNA CO, PENN.
PENN. DEPT. OF MINES & MINERAL INDUSTRIES
SCALE 1"= 100' JANUARY 1968