

P.O.T. Sta. 836+87.68 S.B.

P.O.T. Sta. 840+53.40 N.B.

B.M. #26 Elev. 1653.667
R.R. Spike in 6" Twin Oak
220' Rt. Sta. 841+00 N.B.

DISTRICT	COUNTY	ROUTE	SECTION	SHEET
5-0	SCHUYLKILL	1005	S-5	32 of 51
FOSTER TOWNSHIP				

FINAL
QUANTITIES

REQUIRED LIST

Sta. 833+40 to Sta. 838+00, Rt. N.B.
460 L.F. Bit Conc. Curb
(For Details See Sheet No. 9)Sta. 833+40, Rt. N.B.
30 L.F. 12" A.C.C.M. Pipe (Slope)
1 Slope Pipe Fitting, Type A
7 C.Y. Cl. 2 Exc. (Pipe & Cl. C Bedding)
1 C.Y. Cl. 2 Exc. (Outlet Ditch)Sta. 833+50, N.B.
98 L.F. 24" Cl. III R.C.C. Pipe
07 C.Y. Cl. B Conc. (Type D Edwl, Lt.)
40 C.Y. Granular Material
115 C.Y. Cl. 2 Exc. (Pipe, Edwl. & Cl. C Bedding)
2 C.Y. Cl. 2 Exc. (Outlet Ditch, Rt.)1280 Sta. 833+90 to Sta. 834+75, S.B.
1284 C.Y. Cl. 1 Exc. (Remove Exist. Spoil Pile)
660 C.Y. Emb. (Backfill)Sta. 833+93 to Sta. 834+17, Lt. S.B.
24 L.F. Permanent Barricade, Type BSta. 834+50 to Sta. 835+80, Lt. S.B.
130 L.F. Bit Conc. Curb
(For Detail See Sheet No. 9)Sta. 834+50, Lt. S.B.
40 L.F. 12" A.C.C.M. Pipe (Slope)
1 Slope Pipe Fitting, Type A
9 C.Y. Cl. 2 Exc. (Pipe & Cl. C Bedding)
1 C.Y. Cl. 2 Exc. (Outlet Ditch, Lt.)54# 346 Sta. 834+75 to Sta. 844+35, Lt. S.B.
65 C.Y. Emb. (Backfill Abandoned Mine Slope)
18" BottomSta. 835+00 to Sta. 835+90, Lt. S.B.
99 C.Y. Cl. 2 Exc. (Parallel Ditch, 18" Bottom)Sta. 835+50 to Sta. 836+25, Rt. N.B.
C.Y. Cl. 1 Exc. (Remove Exist. Spoil Pile)
C.Y. Emb. (Backfill)188 Sta. 836+33 to Sta. 836+75, S.B.
194 C.Y. Cl. 1 Exc. (Lateral Benching)
194 C.Y. Emb. (Backfill)
(For U'drain & U'drain Outlets See Tabulation Sheet No. 8)
(For Details See Sheet No. 9)Sta. 836+50 to Sta. 838+50, N.B.
2304 C.Y. Cl. 1 Exc. (Remove Exist. Spoil Pile)
2304 C.Y. Emb. (Backfill)Sta. 836+52 to Sta. 836+76, Rt. N.B.
24 L.F. Permanent Barricade, Type B460 232 917 Sta. 836+55, N.B.
10 L.F. 30" Cl. IV R.C.C. Pipe
10 C.Y. Cl. B Conc. (Type D Edwl, Lt.)
C.Y. Granular Material
C.Y. Cl. 2 Exc. (Pipe, Edwl. & Cl. C Bedding)
8 C.Y. Cl. 2 Exc. (Inlet & Outlet Ditches)
(Max. Fill Over Pipe 40')Sta. 837+25 to Sta. 837+75, Rt. N.B.
430 C.Y. Cl. 1 Exc. (Benching)
430 C.Y. Emb. (Backfill)
(For U'drain & U'drain Outlets See Tabulation Sheet No. 8)
(For Details See Sheet No. 9)112 37 96 88 28 Sta. 837+50, N.B.
1 L.F. 18" Cl. III R.C.C. Pipe
1 Type A Ft. Inlet, Median
C.Y. Granular Material
C.Y. Cl. 2 Exc. (Pipe & Cl. C Bedding)
L.F. 18" A.C.C.M. Pipe (Slope, Rt.)
C.Y. Cl. 2 Exc. (Pipe & Cl. C Bedding)
1 C.Y. Cl. 2 Exc. (Outlet Ditch, Rt.)Sta. 842+38 to Sta. 842+62, Lt. S.B.
24 L.F. Permanent Barricade, Type B

Alignment Book Number 16997 S.B. 16765 & 16995 N.B.

Topo Book Number 16792

X-Sections Book Number 16797

LEON E. KOCHER COAL COMPANY

LEON E. KOCHER COAL COMPANY

