

FINAL QUANTITIES	REQUIRED LIST
140	Sta. 808+63, N.B. 142 L.F. 18" C.I. III R.C.C. Pipe 1 Type 4 Ft. Inlet, Lt. 46 C.Y. Granular Material 137 C.Y. C.I. 2 Exc. (Pipe & C.I.C Bedding)
142	Sta. 812+85, N.B. 160 L.F. 18" C.I. III R.C.C. Pipe 1 Type 4 Ft. Inlet, Lt. 46 C.Y. Granular Material 125 164 C.Y. C.I. 2 Exc. (Pipe & C.I.C Bedding) 2 C.Y. C.I. 2 Exc. (Outlet Ditch, Rt.)
405	Sta. 814+05 to Sta. 814+95, N.B. 416 C.Y. C.I. 1 Exc. (Benching) 405 418 C.Y. Emb. (Backfill) (For U'drain & U'drain Outlets See Tabulation Sheet No. 8) (For Details See Sheet No. 9)
	Sta. 813+00 to Sta. 814+50, Lt. S.B. Escape Taper (Variable 0'-0" to 12'-0" Width) 100 S.Y. Bit. Surf. Crse., 1D-2, 4" Depth 100 S.Y. Bit. Conc. Base Crse., 6" Depth (Sub-base & Subgrade Included in S.B. Rdwy.)
216	Sta. 814+75 to Sta. 816+25, N.B. 193 C.Y. C.I. 1 Exc. (Benching) 216 193 C.Y. Emb. (Backfill) (For U'drain & U'drain Outlets See Tabulation Sheet No. 8) (For Detail See Sheet No. 9)
	Sta. 816+00 to Sta. 824+50, Rt. N.B. Acceleration Lane (Variable 17'-0" to 0'-0" Width) 803 S.Y. Bit. Surf. Crse., 1D-2, 4" Depth 803 S.Y. Bit. Conc. Base Crse., 6" Depth (Sub-base & Subgrade Included in N.B. Rdwy.)
185	00 Sta. 817+50, N.B. 152 L.F. 18" C.I. III R.C.C. Pipe 1 Type 4 Ft. Inlet, Lt. 49 C.Y. Granular Material 18 187 C.Y. C.I. 2 Exc. (Pipe & C.I.C Bedding) 63 C.Y. C.I. 2 Exc. (Outlet Ditch, Rt.)
231	Sta. 819+50 to Sta. 823+25, Lt. S.B. 232 C.K. C.I. 2 Exc. (Parallel Ditch, 18" Bottom)
	<u>RAMP "C"</u> Sta. 8+50, Rt. 80 C.Y. Emb. (Backfill Strip Mine Area)
25	Sta. 9+10 80 L.F. 18" C.I. III R.C.C. Pipe 1 Type 4' Inlet, Lt. 40 26 C.Y. Granular Material 4 187 C.Y. C.I. 2 Exc. (Pipe & C.I.C Bedding) 9 10 C.Y. C.I. 2 Exc. (Outlet Ditch, Rt.)
	Sta. 10+25 to Sta. 15+50, Rt. 525 L.F. Bit. Conc. Curb (For Details See Sheet No. 9)
	Sta. 10+25, Rt. 10 L.F. 12" A.C.C.M. Pipe (Slope) 1 Slope Pipe Fitting, Type A 2 C.Y. C.I. 2 Exc. (Pipe & C.I.C Bedding) 1 C.Y. C.I. 2 Exc. (Outlet Ditch)
35	Sta. 11+17, Rt. 34 C.Y. C.I. 2 Exc. (Remove Exist. Pipe, Inlet & Edwl.)
325	Sta. 12+75 to Sta. 16+01.50 326 L.F. Conc. Traffic Separator, Type A (Sub-base & Subgrade Included in Ramp C Rdwy.)
	Sta. 15+50, Rt. 56 L.F. 12" A.C.C.M. Pipe (Slope) 1 Slope Pipe Fitting, Type A 11 C.Y. C.I. 2 Exc. (Pipe & C.I.C Bedding) 1 C.Y. C.I. 2 Exc. (Outlet Ditch, Rt.)
	Alignment Book Number 16997 S.B., 16765 & 16998 N.B. 17003 Ramps C & D Type Book Number 16983 X-Sections Book Number 16774 & 16775 17003 Ramps C & D

