

NOTE -
ALL DIMENSIONS GIVEN ARE TO FINISHED
GRADE - ALLOW 2" FOR GROUTING.
CONCRETE TO BE 1:2:4 MIX EARLY
STRENGTH. CONCRETE MAX. AGGREG.
3/4". ALL REINFORCING TO BE ROUND
DEFORMED BARS. FOOTINGS DESIGNED
FOR 5000# SOIL PRESSURE.
AFER EXCAVATION PROVIDE
TRENCH DRAINS TO KEEP GROUND
WATER OUTSIDE OF BUILDING
FOUNDATION.

PREPARED DATE	REVISION NUMBER	REVISION DATE	OVERSIGHT	THE PHILADELPHIA & READING COAL & IRON CO. POTTSVILLE, PA. GENERAL ENTERPRISE STRIPPING CLEANED PIT. EXT. A25 GENL. ARREST & DETAILS OF FOUNDATION!! DRAWN: H.W. MEIER CHECKED: <i>Charles A. Jones</i> APPROVED: <i>H.R.H.</i> SCALE: 1" = 1'-0" DATE: 3-5-41 DRAWING NUMBER: 200-2703
------------------	--------------------	------------------	-----------	--