COPING FOUNDATION

7'-8" 7'-8" 7'-3" 7'-3"

ENDS OF ALL BUNTINGS TO BE REMOVED AND POCKETS FILLED WITH BRICKS AND CEMENT MORTAR TO MAKE A WATERTIGHT WALL.

4'-0" INSIDE

LANDING

2'-8" X 10" BUNTING (REMOVE)

3" X 10" GUIDE (REMOVE)

5" X 7" GUIDE (REMOVED)

DOOR

DOOR

SKIP WAY

1'-0"

AIR CURTAIN WALL

H-BEAMS AND AIR CURTAIN WALL TO REMAIN.

RETURN AIR COMPARTMENT

12" WATER PIPE

4" WATER PIPE

FACE OF LINING

OUTSIDE FACE OF FAN HOUSE

GROUT

STONE FAN HOUSE

7'-8" 7'-8" 2'-6" GATE 6'-0" 6'-0"

8'-0" HIGH FENCE (IPAGE, TYPE 3 TR OR SIMILAR QUALITY)

GATE TO OPEN FROM INSIDE; BUT TO OPEN FROM OUTSIDE WITH KEY ONLY.

COPING FOUNDATION

2'-6" GATE

TOP OF GROUT

FENCE SUPPORTS TO BE GROUTED INTO CONCRETE COPING FOUNDATION AS SHOWN.

NOTE:

FENCE AND GATE AT TOP OF SHAFT TO BE FURNISHED AND ERECTED BY WEIRTON COAL COMPANY.

OLD HEAD FRAME

TOP OF COPING — ELEV. 793.7

DETAIL OF TOP OF No 2 SHAFT	
WEIRTON COAL COMPANY	ISABELLA MINE ISABELLA, PA.
DATE: 6-20-38 SCALE: 1/2"=1'-0"	MADE BY: C.W.D.

8-1-41.
REVISED: 7-25-40.

B-652