



PHASE-2
(STEP-1)

BANK REMOVAL	
AREA	
1	41,000 CU. YDS. (COLD)
2	REQUIRED FOR EXCAVATION - (446,000 CU.YDS)
3	241,000 CU. YDS. (32% HOT)
4	125,000 CU. YDS. (HOT)
5	78,000 CU. YDS. (COLD)
	931,000 CU. YDS.

MAMMOTH STRIPPING	
AREA	
3	39,250 CU. YDS - REMOVAL
3	39,250 CU. YDS - BACKFILL
	S-9 TO S-11

This map prepared by L. ROBERT KIMBALL
Consulting Engineers, Ebensburg, Pennsylvania,
by photogrammetric methods using aerial
photography dated APRIL 11, 1967.

TOPOGRAPHIC MAP
OF
KHELEY RUN MINE
FOR
UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF MINES
SHENANDOAH PENNSYLVANIA
SCALE: 1"=100' 2' CONTOUR INTERVALS AUGUST, 1967