



NOTES
 All purlins 6L8x2
 All girts 6L8x2
 All roof rods 3/4 dia.
 All holes 1/2 unless noted
 All rivets 3/4 unless noted
 All steel to be painted one shop coat
 Roofing - 10 ga galvanized corrugated steel
 Siding - 12 ga galvanized corrugated steel
 Floor & step matting - 1/4" x 8"
 Girt steel fixed type covers in frames to fit openings 4" wide by 4" high

Doors to be hollow steel frame with steel sills, rails & pinnae. Complete with hinges, handles & latches if locks.

