



4. THE UNLAPPED EDGE SHALL BE STAPLED AT 6' INTERVALS 5. CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL MATTING UNTIL THE PROJECT HAS BEEN ACCEPTED.


6. JUTE MATTING TO BE USED ON UNPROTECTED SIDE SLOPES
THAT EXCEED 2:1.






TYPICAL JUTE MATTING INSTALLATION (A)


EXCAVATION SCHEDULE						
STATION	А	В	С			
0+00 TO 0+70	55'-8" TO 62'-9"	24'-3" TO 31-10"	10'-7" TO 10'-4"			
0+70 TO 5+00	62'-9" TO 60'-3"	31'-10"	10'-4" TO 9'-6"			
5+00 TO 5+10	60'-3" TO 59'-6"	31-10" TO 31-8"	9'-6" TO 9'-3"			
5+10 TO 10+00	59'-6" TO 61'-8"	31-8"	9'-3" TO 10'-0"			
10+00 TO 10+01	61'-8" TO 62'-11"	31'-8" TO 31-10"	10'-0" TO 10'-3"			
10+01 TO 21+90	62'-11" TO 76'-11"	31'-10"	10'-3" TO 15'-0"			
21+90 TO 22+00	76'-11" TO 75'-9"	31-10" TO 31-6"	15'-0" TO 14'-9"			
22+00 TO 30+00	75'-9" TO 62'-7"	31-6"	14'-9" TO 10'-4"			
30+00 TO 30+50	62'-7" TO 40'-3"	31'- 6" TO 12'- 8"	10'-4" TO 9'-2"			
31+88 TO 32+25	41'-6" TO 63'-5"	17'-0" TO 32'-5"	7'-6" TO 10'-3"			
32+25 TO 32+76	63'-5" TO 65'-2"	32'-5"	10'-3" TO 10'-10"			
32 +76 TO 33 +76	65'-2" TO 30'-0"	32'-5" TO 30'-0"	10'-10" TO 0'- 0"			





SECTIONAL ELEVATION

DERRICK STONE CUTOFF WALL (B)




ALTERNATE 'B'


FOR DIMENSIONS, SEE LINED STREAM CHANNEL SCHEDULE, THIS SHEET.

TYPICAL SECTION-LINED STREAM CHANNEL

LINED STREAM CHANNEL SCHEDULE					
STATION	Α	В	С	RIPRAP DEPTH *	
0+00 TO 0+70	46'-7" TO 55'-7"	7'-7" TO 7'-4"	2'-0"	18"	
0+70 TO 5+00	55'-7" TO 53'-0"	7'-4" TO 6'-6"	2'-0"	18"	
5+00 TO 5+10	53'-0" TO 53'-2"	6'-6"	2'-0"	18"T015"	
5+10 TO 10+00	53'-2" TO 55'-5"	6'-6" TO 7'-3"	2'-0"	15"	
10+00 TO 10+01	55'-5" TO 55'-6"	7-3"	2'-0"	15"T018"	
10+01 TO 21+90	55'-6" TO 69'-9"	7-3" TO 12-0"	2'-0"	18"	
21+90 TO 22+00	69'-9" TO 70'-4"	12'-0" TO 12'-3"	2'-0" TO 4'-4"	18" TO 12"	
22+00 TO 30+00	70'-4" TO 57'-2"	12'-3" TO 7-10"	4'-4"	12"	
30+00 TO 30+50	57'-2" TO 36'-7"	7'-10" TO 8'-2"	TRANSITION	12"	
		No September 187			
31+88 TO 32+25	34'-0" TO 51'-9"	5'-6" TO 6'-0"	TRANSITION	2'-0" DERRICK STONI	
32+25 TO 32+76	51'-9" TO 53'-6"	6'-0"TO 6'-7"	2'-0"	SEE TYP. SECT.	
32+76 TO 33+76	53'-6" TO 30'-0"	6'-7" TO 0'-0"	2'-0"	SEE TYP. SECT.	




STA. 32+25 TO STA. 33+76 ALTERNATES 'A' AND 'B'



STA. 0+70 TO STA. 30+00 ALTERNATE 'A'

TYPICAL SECTIONS-LINED STREAM CHANNEL



CONTRACT NO. SL 139-1-6-101.1

MINE DRAINAGE POLLUTION ABATEMENT
FALL BROOK
LACKAWANNA RIVER WATERSHED
LACKAWANNA COUNTY
PENNSYLVANIA

GANNETT FLEMING CORDDRY AND CARPENTER, INC. Consulting Engineers P.O. BOX 1963 HARRISBURG, PA.

> MISCELLANEOUS DETAILS

MAY, 1977 R.C.L. 10 of 12 NO SCALE D.J. B.

TYPICAL SECTION-STREAM CHANNEL EXCAVATION