

SURFACE +530.00

SAND & LOAM

GRAVEL

FINE SAND

BLUE CLAY

GRAVEL

SLATE & FIRE CLAY

145'

+385.0

+385.35-MINE WATER POOL-FEB. 4, 1964

+328.98-MINE WATER POOL-JAN. 6, 1964

+300

+275.25-MINE WATER POOL-DEC. 3, 1963

+221.94-MINE WATER POOL-NOV. 6, 63

+174.72-MINE WATER POOL-OCT. 9, 1963

SNAKE ISLAND SEAM 8.0 FEET
NOT MINED-SEAM DIRTY

+148.0

+141.37-MINE WATER POOL-SEPT. 11, 63

+108.86-MINE WATER POOL-AUG. 14, 63

+75.63-MINE WATER POOL-JULY 16, 1963

+75.63

ABBOTT SEAM 5.0 FEET
FIRST MINED ONLY-1941-
57% REMOVED

+59.0

+51.48-MINE WATER POOL-JUNE 19, 1963

+13.72-MINE WATER POOL-MAY 22, 1963

DATUM=ZERO

KIDNEY SEAM 7.0 FEET
FIRST MINED ONLY-1948
50% REMOVED

-42.0

-29.40-MINE WATER POOL-APR. 22, 63

-59.80-MINE WATER POOL-MAR. 26, 1963

-89.51-MINE WATER POOL-FEB. 25, 1963

HILLMAN SEAM 12.0 FEET
FIRST MINED ONLY-1945
50% REMOVED

-112.0

-114.72-MINE WATER POOL-JAN. 28, 1963

-136.50-MINE WATER POOL-JAN. 2, 1963

-163.56-MINE WATER POOL-DEC. 4, 1962

-187.66-MINE WATER POOL-NOV. 5, 1962

-203.84-MINE WATER POOL-OCT. 8, 1962

-219.87-MINE WATER POOL-SEPT. 11, 1962

FIVE FOOT SEAM 5.0 FEET
FIRST MINED ONLY -236.29- AUG. 14, 1962
50% REMOVED

-238.0

-264.71-MINE WATER POOL-JULY 2, 1962

LANCE SEAM 7.0 FEET
FIRST MINED ONLY
50% REMOVED
NO MINING BELOW THIS SEAM

-373.0

121'

128'

ROCK STRATA FRACTURED BY SQUEEZE, 1954-1958

COLUMNAR SECTION

SHOWING STRATA BENEATH

RIVERSIDE DRIVE

-BETWEEN-

SHELDON & STANLEY ST'S, WILKES-BARRE, CITY, PA.

PENNSYLVANIA DEPARTMENT OF MINES & MINERAL INDUSTRIES

SCALE-1in=25ft. Vertical

DECEMBER 1962

2