


HOLE NO. 1 DEPTH DRILLED (COMPLETED) 164.0 LFT.
DEPTH DRILLED (BEGINNING) 0 LFT.

DATE DRILLED: 30 JULY 1984 THRU 31 JULY 1984
SURFACE ELEVATION: 788.69

HOLE NO. 2 DEPTH DRILLED (COMPLETED) 178.5 LFT.
DEPTH DRILLED (BEGINNING) 0 LFT.

DATE DRILLED: 23 JULY 1984 THRU 26 JULY 1984
SURFACE ELEVATION: 791.71

DRILLING RUNS (FT.)		% CORE RECOV.
FROM	TO	
0	23	
23	31	81.25
31	41	100
41	43.5	100
43.5	53.5	100
53.5	63	100
63	72.5	100
72.5	81.5	100
81.5	84	100
84	94	100
94	104	100
104	114	100
114	124	100
124	134	100
134	144	100
144	154	100
154	164	55



FIELD CLASSIFICATION OF MATERIALS

FILL

FILL + Boulders

GRAY SANDSTONE
COAL + SHALE

GRAY SANDSTONE
SANDY SHALE

GRAY SANDSTONE
SANDY SHALE

SANDY SHALE w/
SANDSTONE STREAKS

SHALE w/ COAL STREAKS

SANDY SHALE

SANDY SHALE w/
SANDSTONE STREAKS
COAL

GRAY SHALE

COAL
SANDY SHALE
GRAY SANDSTONE


SANDY SHALE w/
BROKEN SHALE

SHALE w/ COAL STREAKS
COAL
GRAY SHALE
GRAY SHALE

WATER LEVEL
NO WATER

LOST WATER
26.8'

DRILLING RUNS (FT.)		% CORE RECOV.
FROM	TO	
0	15	
15	25	80
25	35	95
35	44	100
44	53.5	100
53.5	55	100
55	63	62.5
63	73	83
73	83	100
83	89	100
89	92.3	100
92.3	96.8	100
96.8	104.8	81.25
104.8	114	76.1
114	124	100
124	134	100
134	144	100
144	153.5	100
153.5	163.5	100
163.5	168.7	100
168.7	174	60.38
174	178.5	66.67



FIELD CLASSIFICATION OF MATERIALS

FILL

Boulders

GRAY SANDY SHALE w/
SANDSTONE STREAKS

GRAY SANDY SHALE
DARK GRAY SHALE

GRAY SANDSTONE
COAL + DARK GRAY SHALE

GRAY SANDSTONE

GRAY SANDSTONE
w/
BROKEN SANDSTONE STREAKS

GRAY SANDSTONE
GRAY SANDSTONE w/ SANDY SHALE STREAKS

GRAY SANDSTONE

DARK GRAY SHALE

GRAY SANDY SHALE

GRAY SANDY SHALE w/
SANDSTONE STREAKS

GRAY SHALE
COAL

GRAY SHALE

GRAY SANDY SHALE
COAL

GRAY SANDY SHALE
GRAY BADLY BROKEN
SANDY SHALE

GRAY BADLY BROKEN SHALE

DARK GRAY SHALE
GRAY SHALE

WATER LEVEL
171.0'

LOST WATER
40.0'