



**WALL AND JOINT LAYOUT  
CONCRETE U-CHANNEL PLAN VIEW**  
(SEE SHEETS 21 OF 26 AND 22 OF 26 FOR DETAILS)

**REINFORCEMENT BAR SCHEDULE  
(CONCRETE U-CHANNEL)**

SIZE	MARK	TOTAL (L.F.)	NO.	LENGTH (Ft.)
4	S401	480	40	12'
4	W401	288	24	12'
4	S402	800	40	20'
4	W402	480	24	20'
4	S403	800	40	20'
4	W403	480	24	20'
4	S404	700	40	20' to 15'
4	W404	420	24	20' to 15'
4	S405	800	40	20'
4	W405	480	24	20'
4	S406	720	40	20' to 16'
4	W406	432	24	20' to 16'
4	S407	800	40	20'
4	W407	480	24	20'
4	S408	720	40	20' to 16'
4	W408	432	24	20' to 16'
4	S409	800	40	20'
4	W409	480	24	20'
4	S410	720	40	20' to 16'
4	W410	432	24	20' to 16'
4	S411	800	40	20'
4	W411	480	24	20'
4	S412	800	40	20'
4	W412	480	24	20'
4	S413	800	40	20'
4	W413	480	24	20'
4	S414	800	40	20'
4	W414	480	24	20'
4	S415	800	40	20'
4	W415	480	24	20'
4	S416	800	40	20'
4	W416	480	24	20'
4	S417	800	40	20'
4	W417	480	24	20'

SIZE	MARK	TOTAL (L.F.)	NO.	LENGTH (Ft.)
4	S418	800	40	20'
4	W418	480	24	20'
4	S419	800	40	20'
4	W419	480	24	20'
4	S420	800	40	20'
4	W420	480	24	20'
4	S421	800	40	20'
4	W421	480	24	20'
4	S422	800	40	20'
4	W422	480	24	20'
4	S423	800	40	20'
4	W423	480	24	20'
4	S424	800	40	20'
4	W424	480	24	20'
4	S425	800	40	20'
4	W425	480	24	20'
4	S426	800	40	20'
4	W426	480	24	20'
4	S427	800	40	20'
4	W427	480	24	20'
4	S428	800	40	20'
4	W428	480	24	20'
4	S429	800	40	20'
4	W429	480	24	20'
4	S430	800	40	20'
4	W430	480	24	20'
4	S433	8,155	1,165	7'
4	S434	10,194	1,165	8.75'
4	S435	18,640	1,165	16'
4	S436	10,325	590	17.5'
6	S601	1508	754	2'
4	C401	105	6	17.5'
4	C402	170	34	5'

NO.	DATE	REVISION	APPR.
SUBMITTED			
PROJECT DESIGNER, WILKES-BARRE			
APPROVED			
CHIEF, DESIGN SECTION, WILKES-BARRE			
COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION			
CONTRACT NO OSM 35(2080)102.1			
STREAM CHANNEL REHABILITATION STERRY CREEK SOUTH JESSUP BOROUGH LACKAWANNA COUNTY, PENNSYLVANIA			
REBAR SCHEDULE & U-CHANNEL PLAN VIEW			
DRAWN BY G.P.F.	DATE OCT. 2, 1996	DRAWING NO. 20 of 26	
CHECKED BY L.J.	SCALE 1in. = 20ft.		

ALL DIMENSIONS AND EXISTING CONDITIONS SHALL BE CHECKED AND VERIFIED BY CONTRACTOR AT THE SITE.