



NOTE: TIE WIRE TO BE SOLID ANNEALED SOFT COPPER
 EACH TIE REQUIRES FROM 3 TO 4 FEET OF WIRE
 TIE WIRE: #4 B & S FOR #4 TO #10 B & S
 #2 B & S FOR #2/0 B & S AND LARGER

PIN INSULATOR TIE
 TOP GROOVE

ENGINEERING DEPARTMENT
 SUSQUEHANNA COLLIERIES COMPANY
 LYTLE COAL COMPANY

Wilkes Barre PA 2-23-1928 SCALE 1/2 Size

DRAWN BY Dougher

CHECKED BY

APPROVED

DR NO 66-525