



Ohio Brass Co. Cat. # 25623 Type D
 Brown Porcelain Suspension Strain Insulator
 Working Strain 3000 Lbs.
 Dry Flash Over Voltage 85,000
 Wet Flash Over Voltage 50,000
 No. per Crate - 6 or 8
 Net weight each 9 Lbs.

NEW Insulator 6/20/58
 Line Material # NS2A2

NOTE: - 4-Units ON STEEL - Strain
 3-Units ON Wood - Strain
 3-Units - Suspension

SUSPENSION STRAIN INSULATOR - 22 KV

ENGINEERING DEPARTMENT
 SUSQUEHANNA COLLIERIES CO.
 LYTLE COAL CO.

Wilkes Barre, PA 2-23-1928 SCALE

DRAWN BY *Eftough*

CHECKED BY

DR. No 66-538

APPROVED *[Signature]*

OK 8/17/31