



PARTS REQUIRED PER 10FT. COL SECTION

ITEM	SYMBOL	QUAN	DESCRIPTION	MATERIAL
8		2	TUBE CONN. BEARING	BRONZE S.A.A. 63
7		2	COLUMN FLANGE	SS 304
6		24	COL FLANGE BOLT & NUT	SS 303
5A	SEE NOTE		TUBE CENTERING SPIDER	SS 304
5		1	ALIGNING RING	SS 304
4		1	STL PIPE RUBBER LINED & COATED	CARB. STL
3		2	SHAFT ENCLOSING TUBE	SS 304
2		1	DRIVE SHAFT	CS 1045 SS 303
1		1	SHAFT COUPLING	SS 303

NOTE: MAX INTERVALS 70 FEET

LIST OF MATERIAL		REVISIONS
DR P.W.A.	FINISH SYMBOLS	
TH P.W.A.	1 EXTRA SMOOTH FINISH	
ENG P.W.A.	2 SMOOTH MACHINE FINISH	
APP J.E.H.	3 MEDIUM MACHINE FINISH	
	4 ROUGH MACHINE FINISH	
	1/164 ALLOWABLE TOLERANCE ON FRACTIONAL FINISH DIMENSIONS	
	0.005 ALLOWABLE TOLERANCE ON SINGLE DECIMAL DIMENSIONS	
	DATE 12-10-58	

4MD 3917 APR 6 1959

Fairbanks, Morse & Co.
POMONA PUMP WORKS
SECTIONAL ILLUSTRATION
16" O.D. x 6" x 3 15/16" FLG. COL. JOINT
ASKAM SHAFT-TRUESDALE COLLIERY
GLEN ALDEN CORP.
LUZERNE COUNTY, PA.
P&M 2048 DSR 311-14