

REQUIRED LIST

- Sta. 1724+85 to Sta. 1725+30
100 S.Y. 9" Unif. R.C.P. for Replacement
25 C.Y. Exc. Cl. 1- Old Pav. Removal
- Sta. 1725+65
1-Vert. Ft. Rebuilt Inlet Lt.
Extend existing End Wall
1 Vertical Ft. Rt.
- Sta. 1726+00
35 S.Y. 6"x6" Pl. Conc. Pav. (27'-1" Apron Rt.)
5 C.Y. Fill- Grade Drive Rt.
- Sta. 1726+50
1-Vert. Ft. Rebuilt Inlet Lt.
- Sta. 1726+50
5 S.Y. 6"x6" Pl. Conc. Pav. (45'-1" Apron Lt.)
- Sta. 1727+65
2 C.Y. Exc. Cl. 1- Grade Drive Lt.
- Sta. 1729+70
4'-15" R.C.P. Extend Present Pipe Lt.
1-A' Ew. Lt.-
2 C.Y. Exc. Cl. 1- Inlet Slope
3 C.Y. Exc. Cl. 2- Ew. Removal
- Sta. 1729+85
5 C.Y. Fill- Grade Drive Rt.
- Sta. 1729+85
3 S.Y. 6"x6" Pl. Conc. Pav. (27'-1" Apron)
- Sta. 1729+85 to Sta. 1730+00
45 S.Y. 9" Unif. R.C.P. for Pav. Replacement
12 C.Y. Exc. Cl. 1- Old Pav. Removal
- Sta. 1730+50
10 C.Y. Exc. Cl. 1- Grade Rd. Appr.
- Sta. 1730+50
12 S.Y. 6"x6" Pl. Conc. Pav. (108'-1" Apron)
- Sta. 1731+00
5 C.Y. Exc. Cl. 1- Grade Drive Lt.
- Sta. 1732+15
4'-30" R.C.P. Extend Present Pipe
1-A' Ew. Lt.-
2 C.Y. Exc. Cl. 1- Inlet Slope
4 C.Y. Exc. Cl. 2- Ew. Removal
- Sta. 1735+30
5 C.Y. Exc. Cl. 1- Grade Drive Lt.
- Sta. 1737+10 to Sta. 1737+40
2 C.Y. Exc. Cl. 2- Curb Removal Rt.
- Sta. 1737+20 to Sta. 1743+20
50 C.Y. Exc. Cl. 1- Grade Drive Lt.
- Sta. 1737+25
85 S.Y. 9" Unif. R.C.P. for Bridge Appr. Rt.
- 50 S.Y. 9" Unif. R.C.P.
to be placed as directed
13 C.Y. Exc. Cl. 1- Old Pav. Removal.
- Sta. 1725+
25 C.Y. Fill
Grade Drive to R.R. Rt.
- Sta. 1726+00 to Sta. 1727+
Modify shoulders on Right as indicated
on the Cross Sections
- Sta. 1726+25
5 C.Y. Fill
Fill Cellular Entrance to R.R. Station Rt.
- Sta. 1726+ Rt.
Place 3 Guard Posts on right shoulder
adjacent to R.R. Station

