

REQUIRED LIST

Sta. 51+75 to Sta. 53+50
Drive Rt.
190 C.Y. Emb.
28 C.Y. Sel. Mat'l. Surf. (Max. Depth 6")

Sta. 53+60 to Sta. 54+80
Drive Rt.
144 C.Y. Emb.
17 C.Y. Sel. Mat'l. Surf. (Max. Depth 6")

Sta. 54+93
5 C.Y. Emb. Block Inlet End of
Existing Pipe
5 C.Y. Cl. 2 Exc. (Stone Box Removal)

Sta. 59+40 to Sta. 62+75 Lt.
63 C.Y. Cl. 2 Exc. (Parallel Ditch 1.5' Bottom)

Sta. 58+70 to Sta. 63+85 Lt.
1530 C.Y. C.I. Exc. (Widened Cut)

Sta. 59+43
80 L.F. 24" R.C.C. Pipe
1.4 C.Y. Cl. B Conc. DE Edwl. Lt.
90 C.Y. Cl. 2 Exc. (Pipe & Edwl.)
8 C.Y. Cr. Aggr. Base Crse. AP
4 C.Y. Cl. 1 Exc. (Base Replacement)

Sta. 62+92
96 L.F. 18" R.C.C. Pipe
1.0 C.Y. Cl. B Conc. DE Edw. Lt.
8 C.Y. Cr. Aggr. Base Crse. AP
4 C.Y. Cl. Exc. (Base Replacement)
70 C.Y. Cl. 2 Exc. (Pipe & Edw.)
10 C.Y. Cl. 2 Exc. (Outlet Ditch Rt.)

Sta. 63+00 to Sta. 63+85 Lt.
15 C.Y. Cl. 2 Exc. (Parallel Ditch
1.5' Bott.)

Sta. 63+93 Drive Lt.
1 C.Y. Sel. Mat'l. Surf. (Max. Depth 6")
18 L.F. 15" C.M. Pipe
5 C.Y. Cl. 2 Exc. (Pipe)

Sta. 64+03 to Sta. 68+15 Lt.
79 C.Y. Cl. 2 Exc. (Parallel Ditch
1.5' Bot.)

Sta. 55+85
84 L.F. 24" R.C.C. Pipe
0.9 C.Y. Cl. B Conc. D Edwl. Lt.
90 C.Y. Cl. 2 Exc. (Pipe & Edwl.
8 C.Y. Cr. Aggr. Base Crse. AP
4 C.Y. Cl. 1 Exc. (Base Replacement)

Sta. 64+03 to Sta. 68+90 Lt.
1279 C.Y. Cl. 1 Exc. Widened Cut