

ELEV. + 663.2

S. 9972-

W. 13.977-

INMAN

B.H. - 161

L & W.B.C.Co.

2" DIAMOND DRILL HOLE DRILLED BY

SURFACE TO RED ASH
STARTED COMPLETED

PITCH - 90°

SCALE 1"=20'

FINE S.S. STONE	12'2"	57'0"
SLATE AND FIRE CLAY	4'6"	61'6"
SAND SLATE	4'0"	65'6"
SAND STONE	2'5"	90'9"
SANDSLATE	3'9"	94'6"
SANDSTONE	5'1"	100'5"
DARK STREAKED SANDSTONE	14'7"	115'0"
SAND STONE	3'9"	118'9"
SHALEY COAL & BONE	1'9"	120'6"
SAND STONE	3'8"	124'4"
BONE	2'0"	126'4"
SAND SLATE	1'2"	127'6"
SANDSLATE & FIRECLAY	3'6"	130'10"
FINE SAND STONE	20'8"	151'6"
COARSE S.S. STONE	24'9"	176'5"
SANDSLATE	13'0"	189'5"
COAL	2'9"	192'0"
BONE	0'8"	192'8"
COAL	0'1"	193'9"
SLATE	0'1"	193'9"
BONE & COAL	1'5"	195'2"
SANDSLATE	0'10"	196'0"
FIRE CLAY	1'6"	197'6"
BONE	0'4"	197'10"
FIRE CLAY	2'2"	200'0"
SAND SLATE	4'6"	204'6"
COAL	3'6"	208'0"
SLATE	0'11"	208'11"
COAL	1'0"	209'11"
BONE COAL	4'1"	214'0"
COURSE S.S. STONE	8'4"	222'4"
SAND SLATE	23'8"	246'0"
COARSE S.S. STONE	5'0"	251'0"
DARK S.S. STONE	1'0"	252'0"
COARSE S.S. STONE	1'0"	253'0"
SAND SLATE	1'7"	254'7"
COARSE S.S. STONE	1'0"	255'7"
SAND STONE	16'5"	272'0"
COAL	2'7"	273'5"
SANDSLATE	2'7"	276'0"
FINE DARK S.S. STONE	18'0"	294'0"
SAND STONE	4'0"	298'0"
COARSE S.S. STONE	14'0"	312'0"
FINE S.S. STONE	0'5"	312'8"
COARSE S.S. STONE	5'4"	318'0"
DARK STREAKED SANDSTONE	5'6"	323'6"
SAND STONE	5'0"	328'6"
BONE	0'2"	328'8"
SLATE	0'5"	329'1"
COAL	0'5"	330'5"
BONE	0'5"	330'10"
COAL	0'1"	332'1"
SLATE	0'1"	332'2"
COAL	0'2"	333'7"
SLATE	0'2"	333'9"
FIRE CLAY	6'3"	340'0"
SAND SLATE	10'0"	350'0"
DARK SAND STONE & FINE DARK STREAKED SAND STONE	10'0"	360'0"
SAND SLATE	8'8"	368'8"
FINE DARK SANDSTONE	17'0"	385'8"
SLATE AND BONE	2'6"	388'2"
COAL	3'5"	391'7"
SLATE	4'0"	395'7"
SAND SLATE	3'8"	399'5"
DARK STREAKED SANDSTONE	6'9"	405'0"
DARK SANDSTONE	26'6"	431'6"
SAND SLATE	9'6"	441'0"
BONE COAL	0'5"	441'5"
SLATE	0'1"	441'6"
COAL	0'3"	441'9"
BONE	0'3"	442'0"
COAL	0'6"	442'4"
BONE COAL	0'6"	442'10"
COAL	0'1"	446'5"
BONE	0'1"	446'5"
SAND SLATE	10'7"	457'0"
FINE DARK SANDSTONE	22'0"	479'0"
SAND STONE	4'1'8"	520'8"
SAND SLATE	5'4"	526'0"
DARK SANDSTONE	3'2"	529'2"
SAND SLATE	2'4"	531'6"
BONE	0'1"	531'7"
COAL	0'8"	532'5"
SANDSLATE	0'8"	533'0"
BONE COAL	2'0"	535'0"
COAL	1'1"	537'6"
SLATE	0'2"	537'8"
SAND SLATE	1'5"	539'1"
FIRE CLAY	4'1"	543'0"
SAND SLATE & FIRE CLAY	22'6"	565'6"
FIRE CLAY	15'6"	581'0"
FINE DARK SAND ST.	2'0"	583'0"
SANDSTONE	2'7"	585'7"
FINE DARK SAND ST.	5'0"	590'7"
SLATE & FIRE CLAY	2'0"	592'7"
SLATE ROCK	3'10"	596'5"
FINE DARK STREAKED SANDSTONE	20'3"	616'8"
DARK SANDSTONE	10'10"	627'6"
SAND STONE	35'10"	663'4"
SAND SLATE	8'6"	671'0"
COAL	0'7"	672'4"
BONE COAL	0'7"	673'9"
COAL	2'0"	675'4"
DARK SANDSTONE	2'0"	677'4"
DARK STREAKED SANDSTONE	25'4"	702'8"
SAND SLATE	4'7"	707'5"
BONE	0'9"	708'0"
COAL	0'6"	708'6"
SAND SLATE	1'8"	709'8"
SLATE ROCK	7'0"	716'8"
SAND STONE	17'9"	734'5"
SLATE	0'5"	735'0"
BONE	0'7"	735'7"
SLATE	0'4"	736'1"
BONE	0'3"	736'6"
SAND SLATE	5'7"	742'1"
COAL	0'2"	742'11"
SLATE	0'5"	742'11"
BONE	0'5"	743'4"
SAND SLATE	1'0"	744'4"
SAND STONE	33'5"	777'9"
STREAKED SANDSTONE	4'0"	781'9"
SAND STONE	27'10"	809'7"
SLATE	0'4"	809'11"
SANDSTONE	21'1"	831'0"
FINE CONGLOMERATE	6'10"	837'0"
SAND STONE	0'9"	837'9"
FINE CONGLOMERATE	1'6"	840'1"
SAND STONE	1'10"	841'11"
FINE DARK SANDSTONE	2'0"	843'11"
SAND STONE	1'7"	845'6"
FINE DARK SANDSTONE	22'1"	867'7"
FINE SANDSTONE	18'8"	886'5"
SAND STONE	8'9"	895'0"
SAND SLATE	0'6"	895'6"
SAND STONE	5'0"	900'6"
SANDSLATE	2'1"	902'7"
SAND STONE	8'1"	910'8"
SAND SLATE	12'0"	922'8"
COAL	0'1"	923'3"
COAL	0'1"	924'5"
BONE	1'0"	925'3"
SLATE	1'1"	927'4"
BONE	0'4"	928'0"
SLATE	1'10"	929'6"
COAL	0'8"	929'11"
SLATE	0'8"	930'7"
COAL	2'3"	930'9"
SAND SLATE	2'3"	930'9"
COAL	0'1"	932'4"
SULPHUR	0'1"	933'5"
COAL	9'8"	936'4"
SLATE & FIRE CLAY	9'8"	946'0"
FINE SANDSTONE	31'6"	977'6"
SAND STONE	22'4"	999'10"
FINE DARK SANDST.	8'2"	1008'0"
SANDSLATE	8'8"	1016'8"
BONE	0'3"	1016'11"
SLATE	0'3"	1017'2"
BONE COAL	0'5"	1017'7"
COAL	0'8"	1020'1"
BONE COAL	0'8"	1020'9"
COAL	0'2"	1023'0"
SLATE	0'12"	1023'3"
SLATE	0'3"	1023'6"
BONE	0'9"	1024'3"
FINE DARK SANDST.	12'3"	1036'6"
BONE	0'6"	1037'0"
SLATE	0'5"	1037'5"
BONE	0'8"	1038'1"
SLATE	1'4"	1039'5"
BONE COAL	0'6"	1040'1"
SANDSLATE	15'6"	1055'7"
FINE DARK SANDST.	6'6"	1062'1"
FIRE CLAY	3'0"	1065'1"
FINE DARK SANDST.	10'0"	1075'1"
SAND STONE	1'0"	1076'1"
COARSE SANDSTONE	20'2"	1096'3"
SAND STONE	7'9"	1104'0"
DARK SANDSTONE	6'8"	1110'8"
DARK STREAKED S.S.T.	2'6"	1113'2"
SAND SLATE	9'1"	1122'3"
COAL	0'4"	1122'7"
SLATE	0'2"	1122'9"
BONE COAL	1'1"	1123'10"
SLATE	0'8"	1124'6"
COAL	6'11"	1131'5"
SAND SLATE	2'0"	1133'5"
FINE DARK SANDST.	11'1"	1144'6"
SAND SLATE	9'0"	1153'6"
BONE COAL	0'4"	1153'10"
FINE DARK SANDST.	1'2"	1155'0"
SAND SLATE	9'0"	1164'0"
FINE SANDSTONE	5'6"	1169'6"
SAND SLATE	6'0"	1175'6"
DARK STREAKED S.S.T.	1'6"	1177'0"
SAND SLATE	5'0"	1182'0"
STREAKED SANDST.	1'4"	1183'4"
SAND SLATE	2'8"	1186'0"
SLATE & FIRE CLAY	3'6"	1189'6"
DARK STREAKED S.S.T.	2'0"	1191'6"
SAND SLATE	24'8"	1216'5"
BONE COAL	3'4"	1219'7"
SLATE	1'10"	1220'7"
FINE SANDSTONE	3'0"	1223'7"
FINE DARK SANDST.	11'5"	1235'0"
SAND SLATE	4'10"	1239'10"
BONE COAL	0'10"	1240'5"
FIRE CLAY	3'2"	1243'0"
SAND STONE	50'1"	1293'11"
SLATE	1'0"	1294'11"
BONE & COAL	0'5"	1295'4"
COAL	0'16"	1296'10"
SLATE	0'10"	1297'2"
SAND SLATE	4'5"	1305'7"
FINE SANDSTONE	1'0"	1306'7"
FINE DARK SANDST.	16'5"	1323'0"
SAND STONE	4'9"	1327'9"
COARSE SANDSTONE	9'8"	1337'5"
SLATE	0'1"	1338'0"
SAND STONE	20'9"	1358'9"
DARK STREAKED S.S.T.	4'0"	1362'9"
BONE & COAL	1'6"	1364'5"
BONE	0'8"	1364'11"
SAND SLATE	13'1"	1378'0"
DARK SANDSTONE	2'0"	1380'0"
SAND SLATE	1'0"	1381'0"
SLATE	3'2"	1384'2"
COAL	1'3"	1386'5"
BONE COAL	0'3"	1386'8"
COAL	1'10"	1388'6"
SLATE & FIRE CLAY	1'6"	1390'0"
FINE SANDSTONE	9'0"	1399'0"
SAND SLATE	7'2"	1406'2"
BONE COAL	0'8"	1406'8"
SAND SLATE	16'9"	1423'5"
DARK SANDSTONE	2'7"	1426'0"
FINE DARK SANDST.	12'3"	1438'3"
BONE COAL	0'6"	1438'9"
SLATE	1'8"	1440'5"
COAL	0'7"	1440'6"
SLATE	0'7"	1441'1"
COAL	9'2"	1453'9"
HARD SANDST.	20'3"	1474'0"
FINE CONGLOMERATE	3'0"	1477'0"
DARK SANDSTONE	4'4"	1481'4"
FINE CONGLOMERATE	20'1"	1501'5"
HARD COARSE S.S.T.	13'4"	1514'9"
BONE COAL	0'1"	1514'10"
SLATE	0'4"	1515'2"
COAL	4'8"	1519'10"
SAND SLATE	7'7"	1527'5"
SAND STONE	1'7"	1528'0"
DARK STREAKED S.S.T.	4'0"	1532'0"
SAND STONE	5'6"	1537'6"
PEA CONGLOMERATE	3'6"	1542'0"
SAND STONE	5'8"	1547'8"
FINE SANDSTONE	13'2"	1560'10"
BONE	0'10"	1561'8"
SLATE	10'11"	1572'7"
SAND STONE	38'10"	1611'5"
FINE SAND ST.	21'1"	1632'6"
COAL	0'8"	1633'0"
SLATE	0'8"	1633'8"
COAL	0'2"	1635'8"
BONE COAL	0'6"	1640'11"
COAL	1'0"	1641'4"
FIRE CLAY	1'0"	1642'4"
SAND SLATE	11'0"	1652'4"
SAND STONE	11'8"	1664'0"
SLATE	1'0"	1665'0"
HARD FINE SANDST.	19'7"	1684'7"
SAND SLATE	2'0"	1686'7"
SLATE	0'10"	1687'5"
SAND STONE	1'7"	1689'0"
SLATE	0'6"	1690'6"
HARD FINE SANDST.	4'8"	1691'2"
SAND SLATE	13'8"	1709'6"
COAL	0'5"	1710'11"
SLATE	0'2"	1710'11"
BONE	1'0"	1711'7"
COAL	0'3"	1713'9"
SLATE	0'3"	1713'11"
BONE	0'6"	1720'5"
COAL	0'3"	1720'9"
SLATE	1'7"	1722'4"
COAL	1'1"	1723'5"
BONE	0'4"	1723'9"
FINE DARK S.S.T.	1'8"	1725'5"
SAND SLATE	1'5"	1726'10"
FINE DARK S.S.T.	16'2"	1743'0"
SANDSTONE	11'4"	1754'4"
SLATE	7'8"	17624