



FAN DATA
 Location: NO. 2 ENTRY - OFFSET 15 FT. (MINIMUM)
 Mfr. JEFFREY Fan Type: 6F-42 AERODYNE
 Size: 42 INCH R.P.M. 1,350
 Water Gage Reading: 1.5
 Air Quantity: 37,590 C.F.M. EXHAUSTING
 Blade Setting: FIXED
 Horsepower: 20 Voltage: 440 Amperes: 49/24.5

**Valley Coal Company
Valley No. 8 Mine**

Permit No. 367M030
 Seam Mined: Lower Freeport
 Status: Completed Circa 6-1-69
 No Visible Discharges

BENCHMARK FROM U.S.G.S. ELEVATIONS
 SET ON STATION 3 LOCATED ON ROOF
 OF CANOPY OF NO. 3 ENTRY - 1687.87

Working Section: 001
 Section Name: South Mains
 Miner: Lee Norse 28 H

AIR READINGS
 ① 14,520 c.f.m.
 ② 19,800 c.f.m.
 ③ 37,590 c.f.m.

Working Section: Proposed
 Section Name: 1st Left Butt
 off South Mains

Miner: Lee Norse 28 H (Miner To
 Be Moved To This Section From Section 001.
 Section 001 Will Be Temporarily Abandoned
 Until An Additional Mining Unit Is Procured.)

ACREAGE LEGEND

- Approximate Regions Of Unmineable Coal (Less Than 32" Thickness) 20,095 Acres
- Areas Of Mineable Coal Reserves (Assumed) 155,805 Acres
- Areas Mined To September 1, 1982 3,560 Acres

Remaining Reserve Acreage = 155,805 Acres
 Minus 3,560 Acres
 = 152,245 Acres

VALLEY COAL COMPANY

VALLEY NO. 14 MINE
 LOWER FREEPORT COAL SEAM
 SITUATE IN
 PINE TOWNSHIP, INDIANA COUNTY,
 PENNSYLVANIA

Scale: 1" = 200'

PREPARED BY
PENN-BRITANNICA CONSULTANTS
 BOX E, ARMAGH, PA 15920

September 1, 1982