



NOTE:
SKETCH SHOWS PROPOSED GENERAL PLAN OF MINE FOR FUTURE DEVELOPMENT.
ALL HEADINGS (BOTH 2-ENTRY AND 3-ENTRY) ARE ON 60' CENTERS. ALL ROOMS TO BE WORKED ON 30' CENTERS. THE GENERAL DIRECTION OF ROOM DEVELOPMENT IS INDICATED BY ARROWS IN EACH PANEL. THE BUTT ENTRIES AND PANELS OFF MAIN EAST TO BE DEVELOPED AS SHOWN; THE BUTT ENTRIES ADVANCED TO THEIR LIMIT AND ROOM AND PILLAR WORK STARTED AT THE END OF THE BUTT ENTRY AND DEVELOPED TOWARD MAIN EAST. IN THE BUTT ENTRIES AND PANELS OFF MAIN WEST, THE ROOM AND PILLAR WORK ON THE RIGHT SIDE OF BUTT ENTRIES DEVELOPED AS THE BUTT ENTRY ADVANCES AND THE ROOM AND PILLARS OFF THE LEFT SIDE OF THIS BUTT ENTRY DEVELOPED AS THE BUTT ENTRY IS REVERSED. ALL OTHER ROOM AND PILLAR WORK TO BE DEVELOPED AS SHOWN ON SKETCH FOR AREA EAST OF THE MAIN HEADING AND WEST OF PA. ROUTE 259. THIS WORK TO BE PERFORMED DURING GENERAL RETREAT OF MINE. A SUGGESTED WORK SCHEDULE FOR PANELS IS SHOWN IN NUMERICAL ORDER ON THE SKETCH.

SKETCH SHOWING
PROPOSED MINING PLAN
No. 3 MINE - THOMPSON COAL CO.
SITUATE IN

WEST WHEATFIELD TWP., INDIANA CO., PA.

SCALE 1 in. = 100 ft.

DEC. 4, 1956 Revised: May 31, 1957 JWE

LEWIS L. GWIN - CONSULTING ENGINEERS
JOHN W. FOREMAN - MINING ENGINEER
ALTOONA, PA.

REC'D FROM RON LITTLE,
N. CARBON FUEL 19 APRIL 89
WJ