



PIDDICORD

D. ANDERSON.

W. A. McCHESNEY

G. W. LUCAS

DRIVE ENTRIES ONLY MAXIMUM WIDTH 12'
TO A POINT 200' FROM CUT THEN
10' MAXIMUM WIDTH 35' CENTERS

FACE ELEVATION 1025.5
OVERFLOW 10246

WHEN 200' FROM CUT THRU 2 HOLES
TO BE MAINTAINED 20' IN ADVANCE OF
THE FACE AND DIAGONAL HOLES 8'
APART FOR THE SAME DEPTH
THE LAST 50' OF DRILLING BY HAND
#2 ENTRY STOP AT LAST CROSS-CUT
UNTIL AFTER #1 ENTRY IS COMPLETED
THE LAST 10' BEFORE CUTTING THRU
MUST BE HAND MINED

*This plan discussed and
approved 12/20/50
Presented by
J. D. Hamilton
J. D. Bergstrom
R. G. F.
J. R. L.
J. D. L.*

1092-
796