

POT. Sta. 845+91.51 S.B.

POT. Sta. 847+89.24 N.B.

B.M. #27 Elev. 1648.220
R.R. Spike in 6" Oak
213' Rt. Sta. 851+00 N.B.

POT. Sta. 853+44.74 N.B.

POT. Sta. 854+49.28 S.B.

POT. Sta. 857+20.08 N.B.

DISTRICT	COUNTY	ROUTE	SECTION	SHEET
5-0	SCHUYLKILL	1005	S-5	34 of 51
FOSTER TOWNSHIP				

FINAL
QUANTITIES

REQUIRED LIST

Sta. 844+25 S.B. to Sta. 848+00 N.B.
Roadway Embankment To Be Rock,
Available From This Project, To
Elev. 1660.0 Lt. S.B. & Elev. 1654.0
Rt. N.B.
(See X-Sections & X-Hatched
Area On Plan)

619

Sta. 844+35 to Sta. 855+08, Lt. S.B.
-592 C.Y. Cl. 2 Exc. (Parallel Ditch,
24" Bottom)

194

Sta. 844+44 to Sta. 844+88, S.B.
-204 C.Y. Cl. 1 Exc. (Lateral Benching)
-204 C.Y. Emb. (Backfill)
(For U'drain & U'drain Outlets
See Tabulation Sheet No. 8)
(For Detail See Sheet No. 9)

194

Sta. 845+50, Rt. S.B.
86 C.Y. Emb. (Backfill) Abandoned
Mine Slope)

Sta. 846+25 to Sta. 847+70, Rt. N.B.
145 L.F. Bit. Conc. Curb
(For Details See Sheet No. 9)

192

Sta. 846+32, N.B.
-1 L.F. 18" Cl. III R.C.C. Pipe
1 Type 4 Ft. Inlet, Lt.

61

-1 C.Y. Granular Material
-221 C.Y. Cl. 2 Exc. (Pipe & Cl. C Bedding)

Sta. 846+50 to Sta. 847+30, Lt. N.B.
-46 C.Y. Cl. 2 Exc. (Parallel Ditch,
18" Bottom)

402

Sta. 846+55, N.B.
-322 L.F. 24" Cl. III R.C.C. Pipe
0.7 C.Y. Cl. B Conc. (Type D Edwl, Lt.)
-335 C.Y. Granular Material
-164 C.Y. Cl. 2 Exc. (Pipe, Edwl. &
Cl. C Bedding)
-2 C.Y. Cl. 2 Exc. (Inlet Ditch, Lt.)

164

Sta. 847+06 to Sta. 847+30, Rt. N.B.
24 L.F. Permanent Barricade, Type B

177

Sta. 847+20 to Sta. 847+58, N.B.
-176 C.Y. Cl. 1 Exc. (Lateral Benching)
-176 C.Y. Emb. (Backfill)
(For U'drain & U'drain Outlets
See Tabulation Sheet No. 8)
(For Details See Sheet No. 9)

177

Sta. 847+40 to Sta. 848+25, N.B.
55 C.Y. Cl. 1 Exc. (Remove Waste Pile
Material Below Subgrade)
55 C.Y. Emb. (Backfill)

Sta. 847+70, Rt. N.B.
26 L.F. 12" A.C.C.M. Pipe (Slope)
1 Slope Pipe Fitting, Type A
6 C.Y. Cl. 2 Exc. (Pipe & Cl. C Bedding)

Sta. 848+68, S.B.
68 L.F. 18" Cl. III R.C.C. Pipe
2 Type H Inlets, Lt. & Rt.
22 C.Y. Granular Material
-51 C.Y. Cl. 2 Exc. (Pipe & Cl. C Bedding,
(For Details See Sheet No. 9)

61

Sta. 848+75 to Sta. 852+00, Rt. S.B.
-322 L.F. 18" Extra Str. R.C.C. Pipe for
Extra Str. VC Pipe or C.M. Pipe
-209 C.Y. Cl. 2 Exc. (Pipe & Cl. C Bedding)

321

Sta. 851+00 to Sta. 852+68, Lt. N.B.
-46 C.Y. Cl. 2 Exc. (Parallel Ditch,
18" Bottom)

220

48

Sta. 851+90, S.B.
-178 L.F. 18" Cl. III R.C.C. Pipe
2 Type H Inlets, Lt. & Rt.
26 C.Y. Granular Material, Pipe or
-59 C.Y. Cl. 2 Exc. (Pipe & Cl. C Bedding)
14 L.F. 18" Extra Str. R.C.C. Pipe or
Extra Str. VC or C.M. Pipe, Rt.)

91

-6 C.Y. Cl. 2 Exc. (Pipe & Cl. C Bedding)
-55 C.Y. Cl. 2 Exc. (Outlet Ditch, Rt.)
(For Details See Sheet No. 9)

4

54

Sta. 852+75 to Sta. 855+86, Lt. N.B.
-63 C.Y. Cl. 2 Exc. (Parallel Ditch,
18" Bottom)

96

Required List Continued on Sheet No. 35

Alignment Book Number 16997 S.B., 16965 & 16996 N.B.

Topo Book Number 16792

X-Sections Book Number 16776

LEON E. KOCHER COAL COMPANY

LEON E. KOCHER COAL COMPANY

