



EMILIE #1 & 2 MINE
EMILIE #3 FAN
3 COMPARTMENT SHAFT
DEPTH OF SHAFT = 119'
JEFFERY 8H96
DIRECT DRIVE
FAN SPEED = 885 R.P.M.
BLADE POSITION = "1"
MOTOR H.P. = 400
MOTOR SPEED = 885 R.P.M.
MOTOR AMPS = 408
MOTOR FULL LOAD = 465
MOTOR VOLTAGE = 440
CYCLE = 60

VOLUMES:
CH 4 %
WATER GAGE
RETURN
INTAKE

(E. F. ROS)

JOHN M. RICHARDSON ET AL

(S. KIMMEL)
ROCHESTER & PITTSBURGH COAL CO.
922S

WILLIAM C. WOOD

M.R. ANKNEY RESERVE-COAL
WILLIAM C. WOOD - SURFACE

MICHAEL R. SCHALL-SURFACE
M.R. ANKNEY RESERVE - COAL

DONALD FLEMING-SURFACE
M.R. ANKNEY RESERVE - COAL

DONALD FLEMING

FLEMING LANDSCAPING CO.

ROCHESTER & PITTSBURGH COAL CO.
909S

ENTRY & CROSS CUTS NOMINAL WIDTHS = 20'
BELT / TRACK ENTRY NOMINAL WIDTH = 22'

POSTED
DEC 01 1994

NOTE: FIRST MINING ONLY ALL
AREAS WITH LESS THAN
100 FT. OF COVER
IN THIS SECTION.

SHADING DEPICTS AREA OF AUXILIARY
SUPPORT FOR 910X AND 805-1X
WHICH SHALL BE INSTALLED AFTER
THE SECTION IS NO LONGER USED.
(CRIB BLOCKS ON 9' CENTERS)