



E SEAM RESERVE-KIM TONNAGE
SOUTH OF WHITESBURG AREA.

46 to 48"	647,000 Tons
44 to 46"	816,000 "
42 to 44"	1,745,000 "
40 to 42"	2,000,000 "
Total	5,208,000 "

Does not include three areas BC
the Road.

SEAM TONNAGE ESTIMATE
PROPOSED "E" SEAM - IDAHO AREA.

46 to 48"	4,430,000 Tons
44 to 46"	9,700,000 "
42 to 44"	8,137,000 "
40 to 42"	5,200,000 "
Total	27,467,000 Tons

Based on 145 Tons per inch area.
@ 60% = 16,500,000 Tons

(E)

LEGEND

- | | | |
|--|------------|---|
| | 48" to 50" | TONNAGE
BASED
ON
1740 TONS
PER FT. AREA |
| | 46" to 48" | |
| | 44" to 46" | |
| | 42" to 44" | |
| | 40" to 42" | |
- E seam projections