

REQUIRED LIST.

- Sta. 166+46 to Sta. 170+47
6587 C.Y. Excav. Type V ditch Lt.
- Sta. 170+47
56'-18" R.C.P.
"DE" Endwall Lt.
10 C.Y. Outlet Excav.
38.62 Cu. ft. "B" Conc.
- Sta. 174+50
48'-18" R.C.P.
"DE" Endwall Lt.
35.31 Cu. ft. "B" Conc.
- Sta. 174+50 to 177+40
3255 C.Y. Excav. Type V ditch Lt.
- Sta. 176+50
45'-36" C.I.P. (Lk. Jt.)
"DE" Endwall Lt.
5 C.Y. Outlet Excav.
To connect to present 36" pipe
63.51 Cu. ft. "B" Conc.
- Sta. 177+40
57'-24" C.I.P. (Lk. Jt.) "B" Conc.
"DE" Endwall Lt. - "A" Endwall Rt.
5 C.Y. Outlet Excav.
To connect to present 24" T.C.P.
5 C.Y. Exc. for Extra Depth
- Sta. 177+40
42'-14" C.I.P. (Lk. Jt.)
5 C.Y. Inlet Excav. to connect
"DE" Endwall 23.71 Cu. ft. "B" Conc.
5 C.Y. Exc. for Extra Depth
- Sta. 176+48 to 177+25
18 Cu. Yds. Exc. Type V Ditch Lt.
- Sta. 177+25
Excav. 3 C.Y. removal
stone box.
3 C.Y. Backfill.
- Sta. 179+38
40'-15" R.C.P.
"DE" Endwall Lt.
40 C.Y. Outlet Excav.
28.33 Cu. ft. "B" Conc.
- Sta. 180+10
10 C.Y. Excav. Grade Rd. Lt.
63 C.Y. Fill " " Rt.
- Sta. 180+20
Relay 25'-16" T.C.P. across
road to Lt.
- Sta. 180+35
51'-45" C.I.P. (Lk. Jt.)
"DE" Endwall Lt.
44 C.Y. Outlet Excav.
19 C.Y. Inlet Exc.
46.73 Cu. ft. "B" Conc.
- Sta. 186+30 to Sta. 187+35
178 C.Y. Excav. Type V ditch Lt.
- Sta. 182+00
36'-42" R.C.P.
"D" Endwall Lt.
17.21 Cu. ft. "B" Conc.
- Sta. 177+50 to Sta. 187+50
Cut- 524 C.Y.
Fill- 749 C.Y.
- Sta. 177+50 to Sta. 180+40
190 C.Y. 4" Tile under drain Lt.
34'30" 4" " Outlets.
- County Commissioners to
arrange for the necessary
removal of all structures
- Sta. 180+28
13.14 C.Y. Plain Conc.
Pave. for Approaches Rt &
Lt. 2 (63'x1')
118'

