

B.M. Spike in Foot of 12" Oak
60' Rt. of Sta 145+65
Elev 1410.162

B.M. Spike in Side of 10" Oak
40' Rt. of Sta 152+35
Elev 1366.676

Div.	County	Route	Appl.	Sheet
3	Schuylkill	755	6615	9 of 15
Union Trp.				

REQUIRED LIST.

Sta. 137+50 to Sta. 147+50
472 C.Y. Exc. for Benching
Slopes on Rt.
472 C.Y. Backfill

Sta. 140+50
111'-16" C.I.P. Lk.Jt.
DE Endwall Lt.
4.4 C.Y. Exc. for Extra Depth
87.42 Cu. ft. B" Conc.

Sta. 144+00
75'-14" C.I.P. Lk.Jt.
DE Endwall Lt.
482 C.Y. Exc. for Extra Depth
31.66 Cu. ft. B" Conc.

Sta. 147+00
63'-14" C.I.P. Lk.Jt.
DE Endwall Lt.
Exc. 3 C.Y. for Extra Depth
32.59 Cu. ft. B" Conc.

Sta. 150+50
69'-14" C.I.P. Lk.Jt.
DE Endwall Lt.
8.03 C.Y. Exc. for Extra Depth
34.49 Cu. ft. B" Conc.

Sta. 152+50
81'-14" C.I.P. Lk.Jt.
DE Lt.
6.94 Exc. for Extra Depth
35.77 Cu. ft. B" Conc.

Sta. 147+50 to Sta. 159+50
556 C.Y. Exc. for Benching
Slopes on Rt.
556 C.Y. Backfill

Sta. 138+50 to 144+00
39.5 C.Y. Boulder Excav.

Sta. 147+00 to 153+00
11.7 C.Y. Boulder Exc.

