



AIR SHAFT No 2 FANS	
DIESEL-STAND-BY	
SIZE:	- 96"
TYPE:	- AERODYNE
MODEL:	- 8-HU
MANUFACTURER:	- JEFFREY
OPERATING WG:	- 3.7"
HP:	- 665
R.P.M.:	- 900

ELECTRIC-OPERATING	
SIZE:	- 96"
TYPE:	- AERODYNE
MODEL:	- 8-HU
MANUFACTURER:	- JEFFREY
OPERATING WG:	- 3.7"
HP:	- 500
R.P.M.:	- 900
EXHAUSTING:	419,130
INTAKE:	315,300
CH:	- 0%

TOP OF COPING ELEVATION: - 950'
 BOTTOM OF COAL ELEVATION: - 617.3'
 DEPTH: - 332.7'
 ELLIPTICAL SHAPE
 MAJOR AXIS: - 25'0"
 MINOR AXIS: - 18'0"

Blade Setting No. 3

FIT TO 8 V

FIT TO 10 V