



CRUCIBLE MINE
NATIONAL MINES CORP.

AIR SHAFT No 3 FANS	
DIESEL-STAND-BY	
SIZE: - 96"	ELECTRIC-OPERATING
TYPE: - AERODYNE	SIZE: - 96"
MODEL: - 8-HU	TYPE: - AERODYNE
MANUFACTURER: - JEFFREY	MODEL: - 8-HU
OPERATING WG: -	MANUFACTURER: - JEFFREY
HP: - 665	OPERATING WG: - 7.7"
R.P.M.: - 900	HP: - 500
	R.P.M.: - 900
	EXHAUSTING: - 352,880
	INTAKE: - 354,730
	CH: - 0%
	BLADE SETTING: - 6 B 6 S
BLADE SETTING: - 6 B 6 S	
TOP OF COPING ELEVATION: - 1091.75'	
BOTTOM OF COAL ELEVATION: - 570.33'	
DEPTH: - 521.42'	
ELLIPTICAL SHAPE	
MAJOR AXIS: - 25'0"	
MINOR AXIS: - 18'0"	