

DISTRICT	COUNTY	ROUTE	SECTION	SHEET
10-0	INDIANA	1054	450 R/W	7 OF 10
BANKS TOWNSHIP				
REVISION NUMBER	REVISIONS			DATE BY

UNOFFICIAL
PRINTS
NOT FINALLY APPROVED
FOR ALIGNMENT OR GRADE

Vertical Curve Description

VPC Station: 286+89.774
Elevation: 520.515
Northing: 5246.358
Easting: 5535.855
Type: Sym. Parabolic
Design Method: External Distance
Length: 354.453
Entrance Grade: -5.420 %
Exit Grade: -0.567 %
Rate of Change: 1.369
Offset From PI: 2.150
Turning Pnt. Stn.: No Turning Point
Turning Pnt. Elv.: No Turning Point
Headlight Sight Distance: 341 FT.
R-value: 7304.455

Vertical Curve Description

VPC Station: 292+45.231
Elevation: 508.765
Northing: 5480.607
Easting: 6039.498
Type: Sym. Parabolic
Design Method: External Distance
Length: 199.438
Entrance Grade: -0.567 %
Exit Grade: 2.482 %
Rate of Change: 1.529
Offset From PI: 0.760
Turning Pnt. Stn.: 292+82.325
Turning Pnt. Elv.: 508.660
Headlight Sight Distance: 388 FT.
R-value: 6542.031

LIMIT OF AUTHORIZATION
STA. 296+50.00
SEG. 100 OFFSET 2171
S.R. 1054 SEC. 450 R/W
BANKS TOWNSHIP
INDIANA COUNTY

