

FORM 8

I.D.No. _____

Borehole Number: OWK-3
 Surface Elevation (Ft/MSL): 1710.89' (ft)
 Borehole Diameter: 8 1/4" inches, From 0.0' To 54.0'
5 7/8" inches, From 54.0' To 97.0'
 Total Depth: 97.0' (ft)
 Depth to Static Ground Water Level (SWL): 74.1' (ft)
 Date SWL Measured: 3/12/91 (mm/dd/yy)

Drilling Method: AIR ROTARY
 Date Drilled: 3/11/91 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: RAS
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water* Observations	Sample No.	Rec'd At	Comments	Well/Pliezometer Construction	Depth (Ft)
60	SOFT, DARK GRAY SHALE							60
64.0'						DRY		
65	SOFT TO MEDIUM HARD, MEDIUM TO DARK GRAY, FINE TO MEDIUM GRAINED SANDSTONE AND INTERBEDDED SHALE					ROD CHATTER AT 64'		65
70								70
75						DRY		75
80								80
86.0'								
85	SOFT, DARK GRAY TO BLACK, CARBONACEOUS SHALE OR COAL					DAMP		85
89.0'								
90	MEDIUM HARD, MEDIUM GRAY, FINE TO MEDIUM GRAINED SANDSTONE (MOSTLY FINE GRAINED)					DRY		90
96.0'								
95	SOFT, DARK GRAY SHALE					DRY TO DAMP		95
97.0'								
	BOTTOM OF BORING 97.0'							
100								100
105								105
110								110
115								115
120								120

*  Encountered Ground Water  Composite Static Water Level

**Recovered/Attempted

F-256
SLW 4/30/91 (2)

Use additional sheets with this format as necessary