

FORM 6

I.D.No. _____

Borehole Number: OWM-2
 Surface Elevation (Ft/MSL): 1703.65' (ft)
 Borehole Diameter: 8 1/4" inches, From 0.0' To 45.0'
5 7/8" inches, From 45.0' To 165.5'
 Total Depth: 165.5' (ft)
 Depth to Static Ground Water Level (SWL): 77.6' (ft)
 Date SWL Measured: 3/8/91 (mm/dd/yy)

Drilling Method: AIR ROTARY
 Date Drilled: 3/5/91 - 3/6/91 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: RAS
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (ft)	Lithologic Description	Plot	Ground Water Observations	Samples No.	Recovery %	Alt.	Comments	Well/Piezometer Construction	Dep (ft)
120	MEDIUM HARD, MEDIUM TO LIGHT GRAY, FINE GRAINED SANDSTONE								120
125									125
130									130
135									135
140							BORING MAKING WATER ~10-15 gpm		140
145							SOME INTERBEDDED, THIN SHALE SEAMS POSSIBLE COAL STREAK AT 148.0'		145
150									150
155									155
160									160
164.0'									
165	SOFT, DARK GRAY SHALE								165
165.5'									
170	BOTTOM OF BORING 165.5'							INSTALLED MONITORING WELL OWM-2 WITH SCREEN SET FROM 143.0' TO 163.0'	170
175									175
180									180

* ▽ Encountered Ground Water ▽ Composite Static Water Level

**Recovered/Attempted

F-256

SLW 4/30/91 ②

Use additional sheets with this format as necessary