

FORM 6

I.D.No. _____

Borehole Number: OWK-4
 Surface Elevation (Ft/MSL): 1710.13' (ft)
 Borehole Diameter: 8 1/4" inches, From 0.0' To 54.0'
5 7/8" inches, From 54.0' To 95.0'
 Total Depth: 95.0' (ft)
 Depth to Static Ground Water Level (SWL): 75.2' (ft)
 Date SWL Measured: 3/12/91 (mm/dd/yy)

Drilling Method: AIR ROTARY
 Date Drilled: 3/11/91 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: RAS
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water* Observations	Sample No. Rec'd At	Comments	Well/Piezometer Construction	Dep (Ft)
0	MINE SPOIL—SOFT, BROWN—GRAY CLAYEY SILT AND ROCK FRAGMENTS				DAMP		0
5							5
10							10
15					BOULDER AT 17' DAMP		15
20							20
25							25
30							30
35					DAMP		35
40							40
45							45
50	SOFT, DARK GRAY SHALE				TOP OF ROCK AT 50.0' WATER COLLECTED IN HOLE WHILE INSTALLING STEEL CASING. SATURATED AT TOP OF ROCK. SET 6 1/4" STEEL CASING AT 54' INTERBEDDED FINE GRAINED SANDSTONE SEAMS DAMP		50
55							55
60							60

* ▽ Encountered Ground Water ▽ Composite Static Water Level

**Recovered/Attempted