

FORM 6

I.D.No. _____

Borehole Number: TB-19
 Surface Elevation (Ft/MSL): 1725.63' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 44.5'
3 1/2" Inches, From 44.5' To 114.0'
 Total Depth: 114.0' (ft)
 Depth to Static Ground Water Level (SWL): 72.2' (ft)
 Date SWL Measured: 12/14/89 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 12/13/89 - 12/14/89 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water Observations	Samples No.	Recovery Alt.	Comments	Well/Piezometer Construction	Depth (Ft)
0	(MINE SPOIL)-MEDIUM STIFF, BROWN GRAY CLAYEY SILT AND SHALE FRAGMENTS, SLIGHTLY WEATHERED, CARBONACEOUS			1	18/18	DRY		0
5				2	14/18			5
10				3	10/18			10
15				4	16/18			15
20				5	18/18			20
24.0'								
25	(MINE SPOIL)-MEDIUM HARD TO HARD, GRAY, SANDY SHALE AND SANDSTONE FRAGMENTS.			6	10/18			25
30				7	17/18			30
35				8	10/18	DRY		35
40				9	2/18			40
42.0'								
45	(MINE SPOIL)-MEDIUM HARD TO HARD, GRAY CLAYEY SILT AND SANDSTONE, VERY BROKEN			10	2/6			45
50				1	2.7' / 9.5'			50
55				2	2.6' / 10.0'			55
60								60

* ▽ Encountered Ground Water ▽ Composite Static Water Level

** Recovered/Attempted

F-256

SLW 2/15/91

Use additional sheets with this format as necessary