

FORM 6

I.D.No. _____

Borehole Number: TB-18
 Surface Elevation (Ft/MSL): 1678.92' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 49.0'
3 1/2" Inches, From 49.0' To 99.0'
 Total Depth: 99.0' (ft)
 Depth to Static Ground Water Level (SWL): 29.0' (ft)
 Date SWL Measured: 2/13/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 2/12/90 - 2/13/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water Observations	Samples No.	Recovery %	Comments	Well/Piezometer Construction	Depth (Ft)
60	SEE PREVIOUS PAGE 62.0'							60
65	MEDIUM HARD, GRAY BROWN, FINE TO MEDIUM GRAINED SANDSTONE WITH CARBONACEOUS SHALE STREAKS, SLIGHTLY BROKEN TO UNBROKEN, MASSIVE			2	10.0' / 10.0'			65
70						NO IRON STAIN		70
75	76.0'			3	10.0' / 10.0'			75
80	MEDIUM HARD, GRAY SHALE, UNBROKEN TO BROKEN							80
85				4	10.0' / 10.0'			85
90	90.0'							90
95	BLACK COAL, BROKEN 91.6'							95
	MEDIUM HARD, GRAY SANDY CLAYSTONE, SLIGHTLY BROKEN TO UNBROKEN, MASSIVE 99.0'			5	10.0' / 10.0'			95
100	BOTTOM OF BORING 99.0'						BORING TREMIE GROUTED WITH CEMENT/BENTONITE MIXTURE UPON COMPLETION OF BEDROCK PRESSURE TESTING	100
105								105
110								110
115								115
120								120

* ☒ Encountered Ground Water ☒ Composite Static Water Level

**Recovered/Attempted

F-256

SLW 2/15/91

Use additional sheets with this format as necessary