

FORM 6

I.D.No. _____

Borehole Number: TB-17
 Surface Elevation (Ft./MSL): 1614.32' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 4.0'
3 1/2" Inches, From 4.0' To 84.0'
 Total Depth: 84.0' (ft)
 Depth to Static Ground Water Level (SWL): 47.8' (ft)
 Date SWL Measured: 2/13/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 2/13/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Driller's License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water Observations	Samples No. Rec'd At	Comments	Well/Piezometer Construction	Depth (Ft)
60	MEDIUM HARD, GRAY, FINE TO MEDIUM GRAINED SANDSTONE, WITH SHALE STREAKS, SLIGHTLY BROKEN TO BROKEN, CARBONACEOUS 74.0'			6 10.0' / 10.0'			60
65							65
70	MEDIUM HARD, GRAY SHALE, WITH FINE GRAINED SANDSTONE STREAKS, SLIGHTLY BROKEN 76.0'			7 10.0' / 10.0'	NO IRON STAINING IN JOINTS		70
75							75
80	MEDIUM HARD, GRAY, FINE TO MEDIUM GRAINED SANDSTONE, WITH SHALE STREAKS, FLAT, UNBROKEN TO BROKEN 84.0'			8 10.0' / 10.0'	80.7' TO 80.9' MUD SEAM		80
85	BOTTOM OF BORING 84.0'					BORING TREMIE GROUTED WITH CEMENT/BENTONITE MIXTURE UPON COMPLETION OF BEDROCK PRESSURE TESTING	85
90							90
95							95
100							100
105							105
110							110
115							115
120							120

* ☒ Encountered Ground Water ☒ Composite Static Water Level

** Recovered/Attempted

F-256

SLW 2/15/91

Use additional sheets with this format as necessary