

FORM 6

I.D.No. _____

Borehole Number: TB-15
 Surface Elevation (Ft/MSL): 1680.90' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 20.5'
3 1/2" Inches, From 20.5' To 70.0'
 Total Depth: 70.0' (ft)
 Depth to Static Ground Water Level (SWL): 12.5' (ft)
 Date SWL Measured: 11/22/89 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 11/21/89 - 11/22/89 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: WAB
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water # Observations	Samples No. Rec'd Att	Comments	Well/Piezometer Construction	Depth (Ft)
60	MEDIUM HARD, GRAY, FINE TO COARSE GRAINED SANDSTONE, MASSIVE, MICACEOUS, SLIGHTLY BROKEN				"ROD CHATTER" AT 60.0' TO 70.0' LOST ALL WATER RETURNS AT 60.0'		60
65	TO UNBROKEN, SOME COAL SPARS, FRESH TO SLIGHTLY WEATHERED, (CONGLOMERITIC) 70.0'			6 10.0' 10.0'	COAL LINED FRACTURE IRON STAINED FRACTURE 68.3' SOME SHALE RIP-UP CLASTS		65
70	BOTTOM OF BORING 70.0'					BORING TREMIE GROUTED WITH CEMENT/BENTONITE MIXTURE UPON COMPLETION OF BEDROCK PRESSURE TESTING	70
75							75
80							80
85							85
90							90
95							95
100							100
105							105
110							110
115							115
120							120

* ☒ Encountered Ground Water ☒ Composite Static Water Level

**Recovered/Attempted

F-256

SLW 2/15/91

Use additional sheets with this format as necessary