

FORM 6

I.D.No. _____

Borehole Number: TB-12
 Surface Elevation (Ft/MSL): 1811.83' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 10.0'
3 1/2" Inches, From 10.0' To 194.0' (ft)
 Total Depth: 194.0' (ft)
 Depth to Static Ground Water Level (SWL): 150.0' (ft)
 Date SWL Measured: 2/7/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 2/6/90 - 2/7/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water Observations	Samples		Comments	Well/Piezometer Construction	Depth (Ft)
				No.	Max. Depth			
0	MEDIUM STIFF TO STIFF, GRAY-BROWN CLAYEY SILT AND SHALE AND SANDSTONE FRAGMENTS, WEATHERED			1	4/18	DRY-MOIST		0
5				2	18/18			5
10				3	11/12	10.0' TOP OF ROCK IRON STAIN ON OPEN FACE OF FRACTURES		10
15	MEDIUM HARD, GRAY-BROWN, FINE TO MEDIUM GRAINED SANDSTONE, WEATHERED, VERY BROKEN TO BROKEN			1	5.85'/9.0'			15
20								20
25				2	10.0'/10.0'			25
30								30
35				3	10.0'/10.0'	28.0' LOST DRILLING WATER 28.7' TO 28.8' MUD SEAM		35
40						IRON STAIN		40
45				4	10.0'/10.0'			45
50	SOFT, BLACK COAL							50
55	MEDIUM HARD, GRAY CLAYSTONE, SANDY, MASSIVE, BROKEN TO UNBROKEN			5	10.0'/10.0'			55
60	SEE NEXT PAGE							60

* ☒ Encountered Ground Water ☒ Composite Static Water Level

**Recovered/Attempted

F-256

SLW 2/15/91

Use additional sheets with this format as necessary