

FORM 8

I.D.No. _____

Borehole Number: TB-4
 Surface Elevation (Ft./MSL): 1697.13' (ft)
 Borehole Diameter: 6" Inches, From 0.0' To 43.0'
3 1/2" Inches, From 43.0' To 189.0'
 Total Depth: 189.0' (ft)
 Depth to Static Ground Water Level (SWL): 71.5' (ft)
 Date SWL Measured: 1/3/90 (mm/dd/yy)

Drilling Method: HOLLOW STEM AUGER & NX WIRELINE
 Date Drilled: 1/2/90 - 1/3/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: MJG
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (Ft)	Lithologic Description	Plot	Ground Water* Observations	Samples No. <u>Recess</u> <u>Alt</u>	Comments	Well/Piezometer Construction	Depth (Ft)
180	MEDIUM HARD, GRAY, FINE TO COARSE GRAINED SANDSTONE, MASSIVE, UNBROKEN TO SLIGHTLY BROKEN						180
185				15	10.0' / 10.0'		185
189.0'							
190							
190	BOTTOM OF BORING 189.0'					BORING TREMIE GROUTED WITH CEMENT/BENTONITE MIXTURE UPON COMPLETION OF BEDROCK PRESSURE TESTING	190
195							195
200							200
205							205
210							210
215							215
220							220
225							225
230							230
235							235
240							240

* ☒ Encountered Ground Water ☒ Composite Static Water Level

**Recovered/Attempted

F-256
 SLW 2/15/91

Use additional sheets with this format as necessary