

FORM 6

I.D.No. _____

Borehole Number: MWM-3D
 Surface Elevation (Ft/MSL): 1676.99' (ft)
 Borehole Diameter: 12 1/4" inches, From 0.0' To 43.0'
7 7/8" inches, From 43.0' To 139.0'
 Total Depth: 139.0' (ft)
 Depth to Static Ground Water Level (SWL): 111.58' (ft)
 Date SWL Measured: 10/26/90 (mm/dd/yy)

Drilling Method: AIR ROTARY-TRI-CONE ROLLER BIT
 Date Drilled: 10/16/90 - 10/18/90 (mm/dd/yy)
 Drilled By: HETAGER DRILLING CO.
 Drillers License Number: 1728
 Logged By: PCM
 County: JEFFERSON COUNTY
 Township or Municipality: PINE CREEK

Depth (ft)	Lithologic Description	Plot	Ground Water * Observations	Samples No. <u>Recovery</u>	Comments	Well/Piezometer Construction	Depth (ft)
120	MEDIUM HARD TO HARD, FINE TO MEDIUM GRAINED, GRAY SANDSTONE, AND INTERBEDDED, DARK GRAY, SANDY SHALE, CARBONACEOUS						120
125							125
130							130
					HIT WATER AT ~132.0'		
135	MEDIUM HARD, REDDISH BROWN, COARSE GRAINED SANDSTONE, IRON STAINING						135
140							140
	BOTTOM OF BORING 139.0'						
145							145
150							150
155							155
160							160
165							165
170							170
175							175
180							180

* ☒ Encountered Ground Water ☒ Composite Static Water Level

**Recovered/Attempted

F-256

SLW 5/2/91 (3)

Use additional sheets with this format as necessary